

General Disclaimer

One or more of the Following Statements may affect this Document

- This document has been reproduced from the best copy furnished by the organizational source. It is being released in the interest of making available as much information as possible.
- This document may contain data, which exceeds the sheet parameters. It was furnished in this condition by the organizational source and is the best copy available.
- This document may contain tone-on-tone or color graphs, charts and/or pictures, which have been reproduced in black and white.
- This document is paginated as submitted by the original source.
- Portions of this document are not fully legible due to the historical nature of some of the material. However, it is the best reproduction available from the original submission.

NASA CR-

141449

PROTOTYPE COLOR FIELD SEQUENTIAL
TELEVISION LENS ASSEMBLY

(NASA-CR-141449) PROTOTYPE COLOR FIELD
SEQUENTIAL TELEVISION LENS ASSEMBLY
Final Report, Nov. 1973 - Oct. 1974
(Radio Corp. of America) 139 p HC \$5.75

N75-14597

Unclass
05001

CSCL 20F G3/74


FINAL REPORT

OCTOBER, 1974

PREPARED FOR

NATIONAL AERONAUTICS AND SPACE ADMINISTRATION
JOHNSON SPACE CENTER
HOUSTON, TEXAS 77058

UNDER CONTRACT No. NAS 9-13688



ASTRO-ELECTRONICS DIVISION
RCA CORPORATION
PRINCETON, NEW JERSEY 08540

PREFACE

This is the final report on the project "Prototype Color Field Sequential Television Lens Assembly", performed for the Johnson Space Center of the National Aeronautics and Space Administration under Contract NAS 9-13688. It covers work performed from November 1973 through October 1974, and responds to the documentation requirements set forth in the Data Requirements List, Item 4 of the contract.

TABLE OF CONTENTS

<u>Section</u>		<u>Page</u>
I	INTRODUCTION AND SUMMARY	1
II	TECHNICAL DISCUSSION	3
	A. Program Objectives	3
	B. Filter Wheel Design	4
	C. Final Design	25
	D. Lens and "C" Mount Considerations	30
	E. Mechanical Design	39
	F. Motor Synchronization and Phasing	44
	G. Color Filter Selection	51
	H. Weight Estimate	57
	I. Performance Data	57
III	ENGINEERING DRAWINGS	62

LIST OF ILLUSTRATIONS

<u>Figure</u>		<u>Page</u>
1	Theoretical Maximum Efficiency Geometry	6
2	Trial Wheel Design No. 1	10
3	Trial Wheel Design No. 2	11
4	Trial Wheel Design No. 3	12
5	Limiting Efficiency as Function of F-Number and Wheel Distance	14
6	Efficiency vs. Wheel Diameter	15
7	Filter Wheel Geometry	17
8	3-Filter Wheel	19
9	Mask Shapes	21
10	Effects of Increased Lens Opening (0.9" Spacing)	24
11	Mask Apertures, 0.15" Spacing	27
12	Mask Aperture, 0.6" Spacing	28
13	Filter Wheel Aperture	29
14	0.15" Mask, Inset in Wheel Aperture	31
15	0.6" Mask, Inset in Wheel Aperture	32
16	Geometry With Included Glass Plate	36
17	Pancake Motor Concept Layout	40
18	Cartridge Motor Concept Layout	41
19	Color Wheel Logic Block Diagram	47
20	Color Wheel Motor Detailed Logic	48

LIST OF ILLUSTRATIONS (Continued)

<u>Figure</u>		<u>Page</u>
21	Color Wheel Motor Timing Diagram	49
22	Overall Spectral Characteristics of Broadcast Camera	53
23	Final Version of Silicon Sensor Response With Revised Spectral Filters and 3000°K Illumination	56

LIST OF TABLES

<u>Table</u>		<u>Page</u>
1	Trial Wheel Designs	9
2	Filter Distance 0.9"; F/4	18
3	Filter Distance 0.2"; F/2	20
4	Six Filters; OD = 2"	22
5	Lens Selection	35
6	Weight Breakdown	58
7	Resolution Data	59
8	Shading Data	60
9	Video Balance	60

SECTION I

INTRODUCTION AND SUMMARY

The Astro-Electronics Division (AED) of RCA submits to NASA this final report covering the design and development of a prototype Color Field Sequential Television Lens Assembly under Contract No. NAS 9-13688.

The primary purpose of this contract is to design, build, and evaluate a prototype modular lens assembly with a self-contained field sequential color wheel. The effort includes the design of a color wheel of maximum efficiency, the selection of spectral filters, and the design of a quiet, efficient wheel drive system.

This report discusses the design tradeoffs considered for each aspect of the modular assembly. Emphasis has been placed on achieving a design which can be attached directly to an unmodified camera, thus permitting use of the assembly in evaluating various candidate camera and sensor designs. A technique is described which permits maintaining high optical efficiency with such an unmodified camera. The recommended implementation of the color wheel assembly uses an edge-driven color wheel and a direct drive (no gearhead) cartridge motor.

A motor synchronization system has been developed which requires only the vertical synchronization signal as a reference frequency input. Equations and tradeoff curves have been developed to permit optimizing the filter wheel aperture shapes for a variety of different design conditions.

The completed hardware, delivered to JSC in October, 1974 consists of a color filter wheel module, an attached remote controllable zoom lens, and a control box which includes the electronics required to operate the color wheel and lens function motors.

The finished hardware demonstrates the viability of providing field sequential color operation in the form of a "kit" attachment for future space missions.

SECTION II

TECHNICAL DISCUSSION

A. PROGRAM OBJECTIVES

The major objectives of the program effort are as follows:

- Develop modular field sequential lens assembly which adapts B&W camera to color.
- Minimize mechanical and electrical interfaces to camera.
- Adapt to standard commercial ("C") mount if feasible.
- Study/optimize filter segment shapes.
- Study/trade-off motor and lens types.
- Fabricate, assemble, test, deliver with associated B&W camera.
- Provide engineering drawings and specifications to permit duplication.

The satisfactory completion of these objectives has provided a modular assembly which can be interfaced with minimal effort to a black and white camera. This in turn allows standardization of camera design for a spacecraft application (e.g., the Space Shuttle) while permitting the conversion to color if and when required by the simple attachment of a module to the existing hardware.

While the final cameras could anticipate such a module and be configured to optimize the interface, we have attempted to solve the more general case. That is, the development of a module which can be attached to any existing standard interface camera. Thus the completed unit could be used for laboratory evaluation of the relative performance characteristics of different cameras and sensor types. This restriction limits the theoretical optical efficiency which can be achieved. The mechanical design was developed to permit easy adaptation to an optimized interface camera with an attendant increase in optical throughput.

To demonstrate the finished performance, the program provides for a standard black and white camera to be supplied and tested with the color wheel module. A 1" (25.4 mm) vidicon format is anticipated as the maximum requirement for the Shuttle or similar space system. Similarly, a silicon target vidicon represents the lowest sensitivity sensor anticipated for use, and also possesses the low lag characteristics needed for field-sequential operation. Accordingly, we selected an MTI Model 55 camera for purchase and use. This camera includes a 1" format silicon vidicon, standard "C" mount lens interface, and remote sync provisions, and is considered to be typical of "standard" available cameras.

B. FILTER WHEEL DESIGN

An important consideration in the design of the Field Sequential Television Lens Assembly is the optimization of the mechanical shape and location of the color filter segments. The ideal goal is to provide maximum efficiency of exposure for a given set of constraints, while maintaining uniform exposure and zero crosstalk from one spectral filter to the other.

The sole function of the filter wheel is to provide color separation; that is, to arrange for light of only one spectral characteristic to strike any point on the faceplate between any two successive scans of the point by the scanning beam. Ideally, then, if the filters could be coplanar with the image plane, the filter mechanism would consist of an endless succession of rectangular filters, moving across the image plane at the same velocity as the scanning lines, with the motion so controlled that successive filter boundaries coincide with successive scan lines. As the filter plane is moved away from the image plane, it becomes necessary, in order to maintain color separation, to provide an opaque bar between adjacent filters of sufficient width to prevent any light from reaching the image plane at the instantaneous location of the scanning line. The resulting limitations can be appreciated with reference to Figure 1.

In Figure 1, scan line separation is shown by showing extrapolated locations of scan lines above and below the raster during retrace time. The required width (B) of each opaque bar is then determined, as shown, by the size of the exit pupil and its distance from the image plane, and by the distance of the filter plane from the image plane. The size of the filter opening (A) is determined by the same geometry, and filter efficiency is given by $A/(A+B)$. It is also clear from the geometry of Figure 1 that there is a maximum separation of filter plane and image plane at which color separation can be achieved.

Equations required to design maximum transmission efficiency filter wheels were initially developed in Appendix A of RCA Proposal No. 102004-A. The equations given in the proposal were modified to take into account the finite distance of lens exit pupil from the image plane.




Figure 1. Theoretical Maximum Efficiency Geometry

These equations were written into a computer program, which was then designed to perform the iterative trial and error process required to achieve maximum transmission efficiency. In summary, the computer program does the following calculation:

Given:

- (a) Raster size (width and height).
- (b) Retrace time (as a percent of total scan interval).
- (c) Distance of lens exit pupil from image plane.
- (d) Distance of filter wheel from image plane.
- (e) Number of sets of three (3) filters installed on filter wheel.
- (f) Maximum lens opening (f-number).
- (g) Maximum diameter of filter wheel apertures.

Using this information, the computer program will determine the significant design parameters for a filter wheel which will have maximum transmission efficiency while still insuring that the active scan line is always masked from direct illumination by the scene. The significant outputs of the program are:

- (a) Separation of filter wheel rotation axis from optical axis.
- (b) Orientation of raster with respect to line joining filter wheel axis and optical axis.
- (c) Transmission efficiency.
- (d) Minimum diameter of filter wheel apertures.

While developing the computer program, a previously unobserved limitation on design parameters was discovered; namely:

$$R \sin P \geq \frac{Y (1-U/S) + U/Q}{2}$$

where R is separation of filter wheel axis from
 optical axis,

 P is angle between line joining these two axes
 and scan line direction,

 Y is raster height,

 U is separation between filter wheel and
 image plane,

 S is distance from lens exit pupil to image
 plane, and

 Q is lens f-number at maximum lens opening.

This relationship effectively establishes a lower limit on the maximum diameter of the filter wheel aperture; but this limit cannot be expressed explicitly because of the trial-and-error nature of the computation.

Optimum filter wheel designs were obtained for a number of trial conditions. In all cases, the following were assumed:

Raster size is 0.375" by 0.500";

Retrace time is 10%;

Lens exit pupil distance from the image plane is 5"; and


Maximum lens opening is f/2.

In all cases except the last three, the number of filter sets was assumed to be two. Output values are shown in Table 1 for a number of values of U (separation between filter wheel and image plane) and OD (maximum diameter of filter wheel aperture). Tabulated outputs are R and P as previously defined, minimum filter aperture diameter (ID), and transmission efficiency (E). The three designs marked with asterisks in Table 1 are shown drawn to scale in Figures 2, 3 and 4.

Additional parametric curves were then prepared, showing the tradeoffs as individual design parameters are varied.


TABLE 1. TRIAL WHEEL DESIGNS

OD U		2 FILTER SETS					3 FILTER SETS
		MINIMUM	1.8"	1.87"	2.0"	2.2"	MINIMUM
.15	R	.486"	.561"		.669"	.777"	.662"
	P	27.7°	44.9°		54.3°	60.0°	21.1°
	ID	.311"	.454"		.706"	.950"	.688"
	E	54%	61%		66%	69%	60%
	OD	(1.649")					(1.99")
.20	R	*.494"	.551"	.589"	.659"	.767"	*.667"
	P	28.6°	43.1°	47.9°	53.7°	59.7°	21.7°
	ID	.304"	.410"	.500"	.664"	.908"	.672"
	E	49%	54%	56%	59%	63%	55%
	OD	(1.685")					(2.02")
.25	R	.502"	.541"		.649"	*.757"	.673"
	P	28.9°	40.4°		53.1°	59.4°	22.0°
	ID	.299"	.366"		.621"	.867"	.662"
	E	45%	48%		53%	56%	50%
	OD	(1.719")					(2.05")




ID = 0.30"
OD = 1.69"
EFF = 49%
WHEEL AXIS TO OPTICAL AXIS = 0.494"
CLEARANCE = 0.2"

Figure 2. Trial Wheel Design No. 1



ID = 0.87 "
OD = 2.20 "
EFF = 56%
WHEEL AXIS TO OPTICAL AXIS = 0.757
CLEARANCE = 0.25 "

Figure 3. Trial Wheel Design No. 2



ID = 0.67 "

OD = 2.02 "

EFF = 55%

WHEEL AXIS TO OPTICAL AXIS = 0.667 "

CLEARANCE = 0.2 "

Figure 4. Trial Wheel Design No. 3

Based on the geometry of Figure 1, with a raster height of 0.375 inch, a duty cycle of 0.9 (10% retrace time) and an exit pupil to image plane distance of 5.728 inches (the value given for the 6 x 13T21 lens), maximum exposure efficiency is plotted in the upper half of Figure 5 as a function of separation between filter wheel and image plane for several values of f-number (f-number is approximately equal to exit pupil distance from image plane divided by exit pupil diameter). This graph clearly shows that for each f-number there is an upper limit on filter wheel distance at which complete color separation can be obtained.

Since overall integrated image plane illumination is proportional to filter efficiency and inversely proportional to the square of f-number, the values plotted in the upper half of Figure 5 have been divided by the square of f-number and replotted in the bottom half of Figure 5. The envelope of the solid lines is shown as a dashed line in this plot, and this represents a measure of the upper limit, as a function of filter distance from the image plane, of the integrated exposure which can be obtained in the image plane with complete color separation.

As has been noted, the graphs plotted in Figure 5 represent upper limits of light efficiency. The geometry upon which they are based (as shown in Figure 1) is appropriate only for a filter wheel of infinite diameter, however. The dependence of filter wheel efficiency on wheel diameter can be seen from the graphs of Figure 6. These have been plotted for the other system parameters as shown in the figure. The maximum efficiencies of 60.8% and 35.4% are shown as the circled points in Figure 5.

It is clear from Figure 6 that filter wheel efficiencies obtainable with reasonable (≈ 2 inches) wheel diameters are significantly, but not prohibitively, lower than theoretical maxima. In the upper half of Figure 5, brackets have been used to show this





Figure 5. Limiting Efficiency as Function of F-Number and Wheel Distance





Figure 6. Efficiency vs. Wheel Diameter

loss for a number of filter distances and f-numbers. In each case, the top of the bracket indicates filter wheel efficiency with an infinite diameter wheel, and the bottom of the bracket gives efficiency with a wheel having a 2-inch maximum diameter of the filter opening.

Several additional trade-off studies have been performed. The parameters involved in these studies are shown in Figure 7. The location of the scanned raster relative to the filter wheel is shown. The distances from the wheel axis to the center of the raster/optical axis is R_1 and the angle between the line joining these axes and the horizontal raster direction is P . OD is the largest diameter of the filter openings, and ID is their smallest diameter. Exposure efficiency is found by swinging an arc through the filter openings with center at the wheel axis; efficiency is then given by arc length within an opening divided by arc length between two successive corresponding edges of filter openings.

The first trade-off studies involved filter diameter (OD) and number of filters per wheel (which may be any multiple of 3). In Table 2, the trade-off is tabulated at $f/4$ for a filter distance of 0.9 inch. OD varies from 1.6 to 2.2 inches, and the number of filters from 3 to 9. Exposure efficiency is expressed here as decimal; the value in parentheses is in each case the decimal efficiency divided by the square of f-number, and represents a measure of overall efficiency. In Table 3, corresponding data are plotted for a lens opening of $f/2$ and a filter distance of 0.2 inch. Examination of these figures shows that efficiency improves with increasing wheel diameter (as shown previously in Figure 6), but over the range of OD covered by the data, the variation is not dramatic. At the 0.9 inch filter distance, efficiency does not change significantly with number of filters, while at the 0.2 inch distance some improvement with decreasing number of filters is seen. Data for six




Figure 7. Filter Wheel Geometry

(6) filters at OD = 1.6 inches and for nine (9) filters at OD = 1.6, 1.8 and 2.0 inches are absent because these configurations are subject to different optimization criteria and are less efficient than direct extrapolation would predict. From Tables 2 and 3 we can conclude that if OD = 2 inches is a reasonable value in terms of space limitations, it is worthwhile considering larger wheels only if substantial (1 or 2 inches) increases in diameter can be tolerated. We can further conclude, with the help of Figure 8 which shows a typical 3-filter design, that efficiency advantages of 3- over 6-filter designs do not outweigh the mechanical disadvantages of complicated filter shape.

TABLE 2. FILTER DISTANCE 0.9"; F/4

OD	No. of Filters	Eff.	ID	R	P
1.6	3	.218 (.014)	.247	.441	63.4°
1.8	3	.235 (.015)	.512	.555	71.3°
	6	.242 (.015)	.293	.523	37.9°
2.0	3	.252 (.016)	.745	.665	75.1°
	6	.257 (.016)	.547	.631	53.7°
2.2	3	.267 (.017)	.964	.771	77.2°
	6	.267 (.017)	.798	.741	61.2°
	9	.271 (.071)	.694	.723	38.7°




Figure 8. 3-Filter Wheel

TABLE 3. FILTER DISTANCE 0.2"; F/2

OD	No. of Filters	Eff.	ID	R	P
1.6	3	.521 (.130)	.372	.466	63.3°
1.8	3	.580 (.145)	.625	.579	69.7°
	6	.529 (.132)	.394	.548	41.9°
2.0	3	.613 (.153)	.858	.689	73.3°
	6	.585 (.146)	.648	.655	53.2°
2.2	3	.634 (.159)	1.082	.796	75.7°
	6	.618 (.155)	.893	.763	59.3°
	9	.593 (.148)	.788	.747	38.9°

Tradeoffs were also performed involving filter distance from the image plane and lens f-number, as shown in Table 4. It is clear from this data that the filter wheel should be placed as close as possible to the image plane (as is indicated also by Figure 5). It also appears that there is not a clear choice between f/4 and f/5 at the 0.9 inch filter distance, but design for f/2 at the shorter distances, despite the lower filter efficiencies, is significantly better in terms of overall efficiency.

The compatibility of designs for the same OD and number of filters, but for different filter distances and f-numbers, was also examined. In Figure 9, it is shown that a single control shape in the wheel can be used to accept masks designed for f/4 at 0.9 inch, f/2 at 0.3 inch and f/2 at 0.2 inch. These are three of the designs for which data is given in Table 4




Figure 9. Mask Shapes

and are those which would probably be used at the designated distances.

TABLE 4. SIX FILTERS; OD = 2"

Filter Distance	f/no.	Eff.	ID	R	P
.9	4	.257 (.016)	.547	.631	53.7°
	5	.366 (.015)	.667	.659	58.0°
.3	2	.448 (.112)	.551	.633	51.1°
	3	.592 (.066)	.681	.663	54.5°
.2	2	.585 (.146)	.643	.655	53.2°
	3	.682 (.076)	.731	.675	54.9°

The effect of arbitrarily increasing the lens opening without changing the filter design was examined for the case of the f/4 opening with filter distance of 0.9 inch. The immediate result is of course that color separation is no longer complete, but the study is complicated by the fact that different points in the image plane are affected differently. Data are plotted in Figure 10 for five image plane locations: the center and the four corners of the raster. Each curve is a plot of instantaneous relative illumination at the image point as a function of filter wheel angular position. For each image point there are three curves: the solid curve for an f/4 illumination cone, the dashed curve for an f/3 illumination cone, and the dot-and-dash curve for an f/2.26 illumination cone. The phase of the filter wheel angular position coordinate

was established for each point to compensate for the fact that the active scan line passes the different points at different times; the result is that the beginning and end of each curve correspond to the times that the scan line passes the point under consideration. When two curves occur near the beginning or end of the time plotted, it means that the point is illuminated simultaneously through two different filter segments.

Associated with each of the fifteen curves in Figure 10 is a set of three numbers separated by slashes. These three numbers represent, respectively, the integrated exposure of the point under consideration to energy transmitted through the preceding filter, the desired filter, and the following filter. The first and last numbers are therefore a measure of crosstalk, while the middle number is a measure of exposure to desired energy. The numbers used here are on the same scale, and therefore directly comparable, with the numbers for overall efficiency given in parentheses in Tables 2, 3, and 4.

As would be expected, the first and third numbers are always zero for operation at $f/4$, since the configuration was designed for complete color separation at this lens opening. However, even at $f/3$, the first and third numbers are significantly non-zero at only one of the five image points, this being the raster corner nearest the filter wheel axis. This means that image plane illumination can be almost doubled (0.028 vs. 0.016) at the cost of only a slight-probably negligible-amount of color crosstalk in one corner of the picture. The effects of further increasing the aperture to $f/2.26$ are clearly more severe in terms of color crosstalk, but until a definite upper limit on crosstalk is established, it is not certain that even this amount of crosstalk will degrade the color performance significantly.




Figure 10. Effects of Increased Lens Opening (0.9" Spacing)

It should be noted that crosstalk may be reduced by use of smaller mask openings in the two channels which provide excessive radiant input. In that case, the results presented would be representative of red crosstalk into blue and green channels, but would be pessimistic for crosstalk from blue and green channels into the others.

The effects of misplacement of the filter wheel axis relative to the raster (errors in angle P of Figure 7) were also investigated. For the wheel designed to operate with an $f/4$ lens opening at a distance of 0.9 inch from the image plane, errors in this angular setting of 10 degrees in either direction produce shading (due to misalignment with the apertures) no greater than 4%, and crosstalk does not exceed 4%. For the filter wheel designed to operate with an $f/2$ lens opening at a distance of 0.2 inch from the image plane, 10 degree misalignments may produce shading errors as large as 15% and crosstalk as large as 10%; but for 5 degree errors in either direction neither of these errors will exceed 5%.

C. FINAL DESIGN

As will be shown in the lens selection/interface section, the effective "C" mount separation can be reduced to 0.6". The closest anticipated separation will be established by the sensor faceplate thickness with added mechanical clearance. For a silicon sensor, the effective optical distance from faceplate to focal plane is 0.113". A design value of 0.15" was chosen to provide mechanical clearance.

The filter wheel aperture dimensions were designed to accommodate the closest anticipated wheel/sensor spacing; mask overlays will provide the required shaping for increased spacing and/or transmission trimming.

Masking aperture shapes and geometry were calculated for the two limiting cases. Figure 11 shows the required shape for condition one (0.15" spacing). The calculated offset angle between the wheel axis and the optical axis is 59.1°, and the offset dimension is 0.750". The angular separation between the upper and lower boundaries is 41.85°; therefore, the optical efficiency can be calculated by comparison to the maximum aperture (60°):

$$\frac{41.85}{60.00} \times 100 = 69.75\%$$

The corresponding shape for condition two (0.6" spacing) is shown in Figure 12. The offset dimension (0.750") is unchanged; however, the required offset angle is now 64.9°. The angular efficiency for this case is:

$$\frac{22.66}{60.00} \times 100 = 37.8\%$$

Since the offset angle is different for the two cases (and for any other case between these two limits) an adjustment method must be provided. The housing design has been made circular to permit rotational adjustment after seating the "C" mount thread. This same adjustment can be used to accommodate the required offset difference angle by aligning the front housing to a different reference mark. For the optimized interface situation, it is assumed that the front housing will be fitted with a quick-disconnect bayonet mount, the separation distance will be fixed, and therefore no angular offset adjustment is required.

An additional consideration is the relative phasing of the filter wheel and the mask shape. The filter wheel opening, shown in Figure 13, was calculated to encompass the mask shape for the two limiting cases. The horizontal line at the top




Figure 11. Mask Apertures, $0.15''$ Spacing




Figure 12. Mask Aperture, 0.6" Spacing




Figure 13. Filter Wheel Aperture

of each mask is designed to be parallel to the scan line at the top of the raster. To insert the 0.15" mask in the wheel aperture, while maintaining nominally symmetric clearance between the mask aperture and the wheel aperture, its reference axes are rotated 2.46° clockwise. This establishes a reference location for the wheel phase detector. If the housing (which contains the phase detector) is now rotated, to adjust the angular offset corresponding to a different aperture/sensor spacing, then the relative phase with respect to the horizontal mask line is similarly rotated.

In turn, this rotation could be corrected for by requiring a different nominal position of the wheel phase detector. Since the phase detector position is adjustable to compensate for system tolerances, additional adjustment range could be provided. An alternate method is to provide the compensating adjustment in the initial insertion of the aperture mask. This eliminates the requirement for readjusting the nominal phase detector position. Following this procedure, the 0.6" mask axes are thus rotated by $2.46^\circ + (64.9^\circ - 59.1^\circ)$, or 8.26° clockwise. Figures 14 and 15 show the two filter masks inserted in the filter wheel openings at their respective angles.

In addition to the nominal mask shapes shown, additional masks are provided, for which the upper and lower boundaries are brought closer together while maintaining the same relative shape. This permits fine trimming of the relative sensitivity of each of the three spectral bands. Coarse balance is provided by using neutral optical density filter segments located in the rear face of the filter wheel.

D. LENS AND "C" MOUNT CONSIDERATIONS

The basic specification for a "C" mount lens interface is defined in USA STD PH22.76-1960. The parameter of importance




Figure 14. 0.15" Mask, Inset in Wheel Aperture




Figure 15. 0.6" Mask, Inset in Wheel Aperture

for this application is the focal distance from the mounting flange to the focal plane which is specified as 0.690" (17.5 mm). Therefore, any camera designed to accept a standard "C" mount lens will have its front flange seating surface set at this exact dimension from the sensor focal plane.

When we attach a color wheel module to such a camera, it must lie forward of the 0.69" dimension. Since many existing cameras do not include provisions for axial adjustment of the sensor focal plane we conclude that the lens used with such a system must be such as to provide a mechanical back focal length of 0.69" plus the thickness of the module. This represents a significant constraint in the choice of a suitable available lens. Further, as discussed in depth in the filter wheel design section of this report, increasing the filter aperture to sensor focal plane spacing imposes a decreasing limit on achievable optical throughput efficiency.

The program objectives to be considered in the lens selection are as follows:

(a)	IRIS	F/2 to F/22
(b)	Focal Length	12 MM to 75 MM (9° - 56° FOV)
(c)	Focus	1 Ft to Infinity
(d)	Format	0.625" Diagonal
(e)	Back Focal Distance	> 1.5"
(f)	Controls	Adaptable for Remote Drives
(g)	Construction	Space Qualifiable Design
(h)	Interchangeability	Lens/Wheel Assembly With Other Commercial Lenses

A survey of existing lens designs was performed to permit selection of an optimum match between the objectives and available designs. The assembled lens data is shown in Table 5. The Angenieux 13-78 mm lens initially appeared to be an optimum selection in terms of parameter compatibility. Further investigation showed; however, that this design is not yet in full production. An engineering model and two prototypes have been delivered for evaluation. Within the next year tooling will be completed and production models made available. This was not compatible with the present program delivery requirements; however, this lens should be considered for future applications. The best alternate selection appears to be the Angenieux 15-90 mm lens which is similar in design to the 12.5-75 mm version which was space qualified on the GCTA program.

In adapting the finished design of the field sequential lens assembly to future space cameras, it can reasonably be anticipated that they can be designed with the sensor mounted flush with the front camera flange. This allows maintaining close sensor to filter aperture spacing (with attendant increase in throughput efficiency), and relaxes the lens back focal length requirement. Since we desire to use the assembly initially with unmodified "C" mount designs, we have explored means to minimize the effects of the 0.69" flange to focal plane distance. Consider Figure 16 which shows the geometry involved. Rays "A" and "B" represent the limiting rays from the exit pupil of the lens as illustrated in Figure 1 (for simplicity of illustration, ray "A" is shown here horizontal; this does not affect the results). If we insert in the optical path a parallel face glass plate (Item 1) with the index of refraction n' , incident rays will be deviated according to their angle of incidence. Ray "B" shown dashed represents the undeviated path without the glass plate. Ray "C" shows the path for a similar ray brought to focus at point P, with the glass plate inserted.

TABLE 5. LENS SELECTION

LENS PARAMETERS							
For- Mat	Focal Range MM	f.#	Mfr.	Field Angle	Near Focus Inches	Weight	Dia x Len Inches
16	17 - 62	2.2 - 22	Angenieux	41° - 11°	48	14 oz	2.05 - 4.55
16	12.5 - 75	2.2 - 22	Angenieux	54° - 9° 30'	48	1½ 3 oz	2.32 - 6.2
16	9.5 - 57.5	1.6 - 22	Angenieux	68° - 13°	24	1½ 13 oz	2.67 - 7.48
16	9.5 - 95	2.2 - 22	Angenieux	68° - 7° 30'	30	3½	3.5 - 8.95
16	12 - 120	2.2 - 22	Angenieux	56° - 6°	60	1½ 14 oz	3.0 - 7.7
16	12 - 240	3.5 - 22	Angenieux	56° - 3°	60	4½ 2 oz	3.94 - 9.8
16	13 - 100	2.0 - 22	Pan Cinor			4½	
16	12 - 120	2.2 - 22	Canon	56° - 6°		2½ 3 oz	
VID	25 - 100	1.6 - 22	Canon		48	2½ 10 oz	3.15 - 7.0
VID	15 - 120	1.3 - 22	Canon		60	8-5½	5.12 - 9.3
VID	15 - 150	2.8 - 22	Canon		60	2½ 5 oz	3.2 - 7.3
VID	15 - 170	2.5 - 22	Canon		77	6½ 4 oz	4.6 - 8.6
VID	16.5 - 95	2.0 - 22	Canon		60	2½ 2 oz	3.0 - 7.1
VID	17 - 85	1.6 - 22	Pan Cinor				
VID	20 - 100	2.1 - 22	Pan Cinor				
VID	25 - 125	2.6 - 22	Pan Cinor				
VID	17 - 130	2.5 - 22	Pan Cinor				

TABLE 5. LENS SELECTION (Continued)

LENS PARAMETERS (Continued)							
For- Mat	Focal Range MM	f.#	Mfr.	Field Angle	Near Focus Inches	Weight	Dia x Lengt Inches
VID	30 - 150	2.7 - 22	Wollensak			6.5# w/Motors	
VID	16 - 80	2.0 - 27	Schnieder				
VID	20 - 100	2.4 - 100	Schnieder			3#	
VID	25 - 150	3.5 - 22	Elgeer			3# 12 oz	
VID	20 - 80	1.8 - 22	Elgeer			2#	
V	16 - 160	1.6 - 22	TTH			17#	
V	16 - 160	3.2 - 22	TTH			5#	
V	Varitol 20	2.2 - 22	TTH			Large	
V	20 - 80	2.5 - 22	Angenieux	43 - 12	48	14 oz	
V	15 - 90	2.5 - 22	Angenieux	55 - 10	48	1# 7 oz	
V	12 - 120	2.6 - 22	Angenieux	67 - 7° 30	30	3#	
V	15 - 150	1.9 - 22	Angenieux	55°-6°	60	2#	
V	25 - 250	3.2 - 22	Angenieux	35 - 3° 30 ¹	60	6#	
V	15 - 300	4.5 - 22	Angenieux	55 - 3°	60	4# 7 oz	
V	13 - 78	2.2 - 22	Angenieux	68°- 13°	24	3#	
V	18 - 130	2.2 - 22	Zoomar		48	4#	




Figure 16. Geometry With Included Glass Plate

We calculate the effective length L' as follows:

$$H = L \tan \phi' \quad (1)$$

$$H = L' \tan \phi \quad (2)$$

$$\text{so } L' = \frac{L \tan \phi'}{\tan \phi} \quad (3)$$

$$L' = \frac{L \sin \phi'}{\sin \phi} \frac{\cos \phi}{\cos \phi'} \quad (4)$$

$$\text{Using Snell's Law } (n \sin \phi = n' \sin \phi'), \quad (5)$$

$$L' = L \frac{n}{n'} \frac{\cos \phi}{\cos \phi'} \quad (6)$$

For small angles of ϕ ($< 20^\circ$), $\cos \phi / \cos \phi'$ is greater than 0.97 and can be approximated by 1.0. Then Equation (6) can be simplified to:

$$L' = L \frac{n}{n'} \quad (7)$$

Typical optical glass index of refraction n' is 1.5. Thus, the effective length L' with the plate installed is $1/1.5$ or $2/3$ of the length L without the plate. The insertion of the plate has two beneficial results for this application. First, the filter aperture position for a given mechanical distance D is effectively reduced by $L/3$. This permits designing a smaller masking width, thus increasing the throughput efficiency. Second, the effective mechanical focal distance F is increased by $L/3$, thus providing increased clearance for the mechanical components of the color filter wheel assembly.

This technique was employed in the final configuration of the module assembly. A compensating glass plate, 0.650" thick, with index of refraction of 1.523 was used to provide an effective separation (filter aperture to focal plane) of 0.6".

E. MECHANICAL DESIGN

Two basic mechanical concepts were studied during this program; namely, an edge driven color wheel using a "cartridge" type motor, and an integral rotor-wheel using "pancake" motor. Investigations have been pursued to establish the tradeoffs in selecting an optimum approach. Initially, the pancake motor system appeared to have the greatest number of advantages. Subsequent continuation of the investigations led to the recommendation of the edge driven system as representing the more optimum implementation. Layout drawings for both systems were generated. The pancake motor concept layout is shown in Figure 17, while the cartridge motor concept is shown in Figure 18. A sample of an existing design pancake motor was obtained from the vendor (Schaeffer Magnetics) for evaluation of magnetic interference and interface effects.

The relative comparison of significant elements between the two systems is as follows:


1. Pancake Motor System

a. Advantages

- Minimum number of bearings (2)
- No gear passes

b. Disadvantages

- Significant magnetic interference with sensor (can be shielded)



COLOR WHEEL w/C-MOUNT LAYOUT
 SCALE: 4X SIZE H.T. MILLER 1/11/74

- ① 2.354 DIA
- ② 2.078 DIA
- ③ 2.203 DIA
- ④ .188

Figure 17. Pancake Motor Concept Layout




Figure 18. Cartridge Motor Concept Layout

- Possible magnetic interference if magnetic wheel position pickup used.
- Inflexible wheel diameter (constrained to available motor diameters).
- Large diameter of stator predicts greater weight.
- High motor vendor start up and repeat order unit cost.

2. Cartridge Motor System

a. Advantages

- No magnetic interference
- Flexible wheel diameter (easily changed by new gear blank).
- Lower weight
- Motor start-up and repeat order unit cost significantly lower.

b. Disadvantages

- Two additional bearings
- One gear pass

In addition to the above items, the fixed stator length of the available pancake motor is somewhat greater than the anticipated path length of the cartridge system. In turn, this tends to restrict the lens selection in terms of back focal length, although acceptable lenses have been identified. Operating power measurements on a sample pancake motor have also been somewhat greater than the equivalent cartridge

motor, although this is not thought to be fundamental to the motor design. Experimental application of magnetic shielding to the pancake motor has reduced the interference effects to indiscernible levels; however, the cost is increased weight in the assembly.

Based on the above consideration the cartridge motor system was chosen as the prime candidate, and detailed design is based on this approach. The cartridge motor concept layouts show that the basic approach is feasible. If future applications were to justify the design expenditure required to overcome the shortcomings noted, it would be a viable approach.

Key items of the pancake assembly shown in Figure 17 are as follows:

1. Main Housing
2. "C" Mount Adapter
3. Filter Wheel
4. Hysteresis Ring Rotor
5. Motor Stator
6. Lens Mounting Flange

Items 1, 2, and 3 are similarly identified for the cartridge layout in Figure 18.

The angular position of the starting thread of the "C" mount is not controlled by specification, therefore, both layouts show a means for rotating the color wheel axis about the optical axis after seating the mating "C" mount thread. If the basic design is extended for future applications to a bayonet or other fixed position mounting attachment, the adjustment feature can be readily deleted without a major design change.

F. MOTOR SYNCHRONIZATION AND PHASING

The lens assembly is required to interface with standard cameras. It can be expected that such cameras can furnish "V" or "H" rate signals for motor sync reference but will not include provisions for adjusting the relative phase of the motor drive and a vertical field. Before proceeding with a final motor selection in terms of operating frequency and number of poles, we examined techniques for motor drive phasing to determine if any bounds need be placed on the selection.

Motor phasing techniques already developed, such as were used in the GCTA cameras (Contract NAS 9-11260) utilize a digital phase shift system to compare and adjust the relative phase of the color wheel and vertical blanking. When the motor sync system is included with the camera sync generator, the implementation was found to be straightforward for a particular value of motor frequency and number of poles (420 Hz and 8, respectively). For the present program the motor phasing system must be considered part of the lens assembly, operable from only the "V" or "H" reference.

The specific pancake motor under consideration was used as a test case; however, general conclusions are drawn from the results. The motor characteristics are:

36 Poles
180 Hz Input
600 RPM

$$1 \text{ pole pair} = \frac{360^\circ}{18} = 20^\circ \text{ shaft rotation}$$

$$1 \text{ pole pair} = 360^\circ \text{ electrical drive shift}$$

Using the original GCTA phasing technique, 90° electrical shift would provide:

$$\frac{20}{360/90} = 5^\circ \text{ position correction}$$

Assuming a six-segment wheel with phase references 180° apart, correction speed for a maximum initial error condition of 180° would be:

$$\frac{180^\circ}{2 \times 5^\circ \times 10 \text{ RPS}} = 1.8 \text{ seconds}$$

The original GCTA design utilized an 8 pole, 6300 RPM, 420 Hz motor with a 10.5/1 gear reduction. This design required 4.2 seconds for phase correction; however, the granularity of each correction step was 2.1° for a 90° shift of the voltage drive. The correction granularity represents a limit on the allowable unused area between wheel segments, and can be reduced by decreasing the amount of electrical shift for each correction step.

The shift is reduced from 90° to 45° by correction at double the original frequency. The tradeoff is in phase correction accuracy versus correction speed, which are in inverse ratio.

In selecting the sync rate to be used in the motor phase comparison, we must consider that the required motor drive frequency, while coherent with both "V" and "H" rates, is not necessarily an integral sub-multiple of the "H" rate. Therefore, a locked oscillator must be used to provide the reference frequency. Since the "V" rate is required for use in the wheel phase comparator it can also be used for the locked oscillator reference. Thus, only a single sync signal need be routed from the camera to the lens assembly.

A block diagram of the selected motor phasing system is shown in Figure 19. Required input signals are the camera "V" rate reference and the wheel position phase reference. The frequency dividers shown are for a 120 Hz motor. Other combinations can be accommodated by changing the division ratio. As shown, the pulse snatching for phase correction is performed at twice the minimum frequency, to provide 2.5P steps for each correction increment.

Using a cartridge motor and a 3/1 gear reduction at the rim drive, a motor speed of 1800 RPM is required. If the motor is designed with 8 poles, the input frequency is 120 Hz, and the block diagram is identical to Figure 19. If a 12 pole design is used, the input frequency required is 180 Hz. This can be achieved simply by changing divider "A" in the block diagram from a $\div 3$ to a $\div 2$. Similarly, other combinations can readily be accommodated by this system.

The detailed logic diagram for the color wheel motor control system is shown in Figure 20 and the related timing diagram is shown in Figure 21. Implementation of the logic functions was accomplished using CMOS logic elements to minimize power consumption.

With regard to the wheel position sensor, a number of different techniques were considered, as follows:

- | | |
|------------|---|
| • Optical | IR emitter and photodetector. |
| • Magnetic | Hall effect packaged with amplifier. |
| • Magnetic | Hall effect sensor and amplifier. |
| • Magnetic | Permanent magnet - with induction coil - available with digital signal conditioning (di-Mag). |




Figure 19. Color Wheel Logic Block Diagram




Figure 20. Color Wheel Motor Detailed Logic




Figure 2L. Color Wheel Motor Timing Diagram

The optical technique has previously been used to perform this function on the GCTA design. The most direct application is to place the source and sensor on opposing faces of the wheel. Since in the present design we are attempting to minimize the sensor/wheel spacing (to maximize throughput efficiency), it is undesirable to locate any portion of the phasing detector behind the wheel. It might be possible to overcome this problem by using a reflective optical technique; however, this is expected to be difficult to implement.

Hall effect devices have been applied as magnetic position indicators in brushless dc motor applications where the magnetic pole piece is inherent in the motor rotor. This technique could be applied here by installing a magnet near the perimeter of the wheel. Recently developed monolithic integrated circuits (e.g., Sprague ULN 3000M) contain a silicon Hall generator and integral amplifier in one small package. However, the Hall sensitivity of silicon is very low (33 mV/kilogauss) and an operating magnet strength of about 500 gauss is required. In addition to the problem of achieving this field strength in a small magnet, it raises the possibility of generating interference in the camera sensor. A GaAs Hall generator is approximately 100 times as sensitive as the silicon device; it could therefore be used with a proportionally smaller magnet. Such a device is not available in a single package; a separate amplifier would be required.

The final method considered is also magnetic, but requires only a ferrous metal perturbation (such as a soft iron slug) to generate an output. It utilizes a small permanent magnet with a concentric induction coil. Passage of the ferrous metal past the pole piece creates an output by induction. Such a device, utilized in the final design, is available in a compact package with included digital interface conditioning under the trade name "Di-Mag", and appears to provide the greatest design freedom.

G. COLOR FILTER SELECTION

1. Introduction

The prototype lens assembly will be demonstrated with the MTI-55 TV camera employing a silicon vidicon. It is anticipated that the bulk of the demonstration as well as evaluation testing will be conducted in an indoor laboratory area where artificial lighting will be employed. This may well correspond to real world Shuttle usage where dark side of the earth operations will employ artificial lighting to permit some measure of direct observation as well as TV coverage.

When a combination usage is planned, a single, properly shaped, trim filter can correct a natural to artificial (or vice versa) condition. Since the case of artificial illumination is expected to require greatest overall system sensitivity, we used that case to compute the spectral filter characteristics, using a silicon target sensor. Provision is included for adding a separate color trim filter, in a holder attached to the front of the lens, to correct the relative R-B-G spectral sensitivities when natural illumination is used. The range of achievable individual filter passbands is large; however, the gamut of existing multi-layer film designs is considerably more restricted. The design is examined within the practical limits of existing interference filters.

Experimental determination of the optimum color wheel filter sequence was established early in the development phase of field sequential television in terms of the affect of image sensor lag. The optimum sequence was found to be R-B-G; that sequence was used for the present modular color wheel assembly development.

Complete details of the spectral filter tradeoffs are contained in the second Engineering Design Report previously submitted under this contract. Salient details are summarized here.

2. Reference Computation

In the process described in the following paragraphs, tungsten illumination at 3000°K is assumed. The colorimetry calculations then consist of cascading the spectral characteristics of tungsten, the sensor spectral responsivity, and all filters employed for spectral separation and ir rejection in each channel. Factors not considered but certainly contributory to color performance in a field sequential system are: incomplete erasure of sensor data in a single (1/60 second) scan due to scan line separation, and inherent retentivity of the target after scanning by the electron beam, i.e., lag. These factors, depending on the effective cross section of the electron beam and the inherent characteristics of the silicon target, may be significant but are more simply treated experimentally.

A colorimetry reference was established by computing the spectral sensitivity of a high quality RCA broadcast camera. This camera employs three Plumbicons and is set-up for indoor operation with tungsten illumination, about 3000°K color temperature.

Spectral separation in this broadcast camera is accomplished with a dichroic prism. The overall spectral response for the three channels of this type camera is shown in Figure 22, where the peak response is normalized.

The numbers appearing under the curves of Figure 22 are normalizing factors required to provide equal peak response. Of course as adjusted in the camera for equal video amplitude on a neutral scene, normalization will require equal areas under the curves. Note that the green channel will have maximum and the blue channel minimum sensitivity.




Figure 22. Overall Spectral Characteristics of Broadcast Camera

3. Color Filters for the Silicon Sensor

The RCA 4532 silicon vidicon has a spectral responsivity that is substantial over the entire visible spectrum and extending into the near ir. When cascaded with the 3000°K tungsten lighting the spectral response shows a continued rising characteristic towards the near ir region.

As a starting point the GCTA color wheel filters, cascaded with the 650 nanometer trim filter and ir rejection filter used on GCTA (RCA assembly drawing 2269728), were cascaded with the silicon at 3000°K response. As a direct result of the rising ir characteristics, the colorimetry of this type filter wheel, as used with silicon and artificial illumination, is considered unsatisfactory for several reasons. The blue channel response is too narrow causing a severe loss in sensitivity as well as poor blue color reproduction. The red response is too wide with excessive green channel overlap again leading to poor colorimetry.

As the next step at arriving at satisfactory colorimetry the red and blue filter characteristics were modified and a different ir rejection filter was assumed. The modified red channel was computed for a 590 nanometer short wavelength Schott glass, and a Fish-Schurman (F-S) 650 trim filter and Schott 1 millimeter HA-11 ir absorbing glass for long wavelength shaping. The characteristic of the ir absorption filter is particularly important when a silicon sensor is employed because of the extended long wave response of this type vidicon. The HA-11 response is less than 3 percent in the 800 to 900 nanometer range.

The computed blue channel response consisted of a F-S 495-C in cascade with a F-S ML-3025S for trimming. The HA-11 was not included in this computation since its effect on the blue

channel is not significant. The 1 MM HA-11 was used for the green computation since it provides some band shaping in the long wavelength portion of the green spectrum.

The composite curves obtained were considered to be quite satisfactory from the colorimetry standpoint. Red-green crossover is comparable to that achieved with the high quality broadcast camera. The blue channel is somewhat narrow but is in the acceptable range. Normalizing factors (for equal peak response) are modest compared to that obtained with the original GCTA filter. Values of 1.0, 1.09, and 2.30 for the red, green, and blue channels respectively are indicative of the relative channel gain required, although adjustment will be made for equal areas rather than equal peak response.

As a final step in the filter specification process, an attempt was made to reduce the number of individual elements required. For this reason the 650 trim assumed for use in the red channel was replaced with the ML 3025-S used with the blue filter. Since this has the effect of extending the red response into the long wavelength end of the spectrum, the 1 MM HA-11 was replaced with the somewhat narrower 2 MM HA-11. The original GCTA green filter (RCA 2262639) was maintained. The overall spectral response of the camera is then as shown in Figure 23.

Note that the overall response is quite similar to that shown in Figure 12 although some slight narrowing of the blue channel has resulted and the red channel is somewhat more asymmetrical. The peak response numbers are slightly closer together than before with the green showing the highest sensitivity. When the area normalization process is taken into account the red channel is most sensitive, with the green requiring 1.11 times and the blue requiring 1.97 times the gain of the red.




Figure 23. Final Version of Silicon Sensor Response With Revised Spectral Filters and 3000°K Illumination

The final filter specification then consists of a filter wheel with a red channel of Schott 570 glass, a green channel as specified for GCTA (RCA 2262639), and a blue channel of F-S 495-C. The specification control drawings for these filters (SK-2277732, 33, and 34) are included in the drawing section. The lens path will employ the F-S 3025-S trim filter and the 2 MM HA-11 ir rejection filter, (SK-2277746) also included in the drawing section. In addition, the red and green filter-wheel segments will incorporate .2 neutral density filters to aid in sensitivity normalization.

Further adjustment of relative gain is obtained by trimming the individual filter-wheel openings. (The trimming process is described in Section B of this report). If all filters are nominal the trimming adjustment will require a reduction by a factor of .81 for the red channel and .90 for the green channel.

H. WEIGHT ESTIMATE

The major component pieces of the color wheel module assembly are listed in Table 6. The associated dimensional drawings were used to calculate the predicted weight of each part by dividing them into geometric shapes. The calculated values are shown in Table 6, and are compared to measurements after fabrication. The front and rear housings will be fabricated of aluminum for the engineering model based on finish and handling considerations. The flight equivalent parts can be fabricated of magnesium with an attendant weight reduction of 35 percent.

I. PERFORMANCE DATA

After completion of fabrication and assembly of the color wheel module, a detailed test program was conducted to provide verification of performance parameters and/or comparison to the program objectives. Certain parameters, e.g., color crosstalk,

TABLE 6. WEIGHT BREAKDOWN

P/N	ITEM	CALCULATED		MEASURED SUB-TOTAL	MTL
		UNIT (LABS)	SUB- TOTAL		
2283447-1	Rear Housing	.2378	.2378	.239	Al
2279971-1	Front Housing	.3517	.3517	.338	Al
2277726-1	Lens Retainer	.0858	.0858	.088	Al
2277718-1	Color Wheel Shaft	.0051	.0051	.0049	S.S.
2277722-1	Clamp	.0119	.0357	.0072	S.S.
2279958-1	Filter Wheel	.1156	.1156	-	S.S.
227773X-1	Filter Segment	.0037	.0441	-	Glass
2273224-1	Comp. Filter	.0287	.0287	-	Glass
58388	Magnetic Sensor	.022	.022	-	-
1971381-2	Motor	.217	.217	-	-
-	Hardware	.10	.10	-	-
2277717-501	Hub and Gear	.0194	.0194	-	-

Color Wheel Assembly Total

1.2629

Lens (6 x 15B)

1.167 lbs

Remote Function (100 grams each)

.661 lbs

are associated solely with the field sequential system. These were measured with the color wheel module installed. Other parameters, such as resolution, are common to the black and white system. These were measured with and without the color wheel module installed, and comparative data obtained. A test procedure (RCA TP-2279979) was generated to specify test methods and record data. The measured performance shows that the desired objectives have been satisfactorily achieved.

The more important data items are summarized below:

a) Resolution

Data was measured with the zoom lens attached directly to the camera, and then with the filter wheel module inserted and operating. The results are shown in Table 7.

TABLE 7. RESOLUTION DATA

RES LINE NO.	B&W	R-1	B-1	G-1	R-2	B-2	G-2
200	51	51	52	52	52	51	53
300	20	20	20	20	20	20	20
400	6	6	6	6	6	6	6

The deviations are negligible and within measurement accuracy, verifying that no resolution degradation is introduced by the filter wheel module.

b) Shading

Data was similarly obtained, with and without the filter wheel module. The results are shown in Table 8.

TABLE 8. SHADING DATA

POINT OF MEASURE- MENT	PERCENT B&W	SHADING FILTER MODULE
20% From Top	32	32.9
50% From Top	25.7	25.2
80% From Top	37	35.9
Vertical	14.9	14.9

Again, negligible change in shading performance is noted.

c) Video Field Balance

To verify the adjustment (trim) balance between the individual spectral filters, the data shown in Table 9 was obtained. The measurements confirm the ability of the filter aperture trim masks to be used in setting individual field signal amplitudes.

TABLE 9. VIDEO BALANCE

FIELD	P-P VIDEO (VOLTS)	% FROM NOMINAL
R 1	0.98	2
B 1	0.97	3
G 1	1.01	1
R 2	0.99	1
B 2	0.97	3
G 2	1.02	2

d) Jitter



The jitter caused by the rotation of the filter wheel is a measure of the parallelism achieved in assembling the individual filter segments to the filter wheel. An objective specification of 0.25 μ s was established. Measurements showed no detectable jitter for five of the six segments. The sixth one measured 0.02 μ s which is well within specification.

e) Filter Wheel Efficiency

The filter wheel efficiency was measured by recording the video signal for a particular color segment, with and without the wheel rotating. The previously calculated value for the 0.6" spacing case was 38 percent. The measured value was found to be 44 percent, slightly better than predicted. This difference may be attributable to tolerances in the mask fabrication, although the exact cause could not be determined.

SECTION III
ENGINEERING DRAWINGS

The following pages contain copies of the applicable engineering drawings for the various components and assemblies which constitute the color lens assembly and its associated control box.



SECTION A-A

NOTES

1. FINISH: PASSIVATE, 1980032

REPRODUCIBILITY OF THE
ORIGINAL PAGE IS POOR

FOLDOUT FRAME /

DIMENSIONS ARE IN INCHES AND
INCLUDE THICKNESS OF PLATING.

TOLERANCES ON FINISHED DIMENSIONS
UNLESS OTHERWISE SPECIFIED

BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS
UP TO 6	±.02	±.005
ABOVE 6 TO 24	±.03	±.010
ABOVE 24	±.06	±.015

ANGULAR DIMENSIONS ±1/2°

SEE RCA PURCH SPEC FOR STOCK TOL

1		
DASH		
QTY REQD	QTY REQD	
504	503	
CONTRA		
COMMO		
DRAWN		
CHECKED		
DESIGN		

FIRST MADE FOR	USED ON
NEXT ASS'Y	COLOR CAM.
2263641-501	

ALL EXTERNAL THREADS TO BE CLASS 2A
BEFORE PLATING, AND CLASS 2 AFTER
PLATING. ALL INTERNAL THREADS TO BE
CLASS 2B, UNLESS OTHERWISE SPECIFIED.

↓ 1974052

WAS

REVISIONS

SYM	ZONE	DESCRIPTION	DATE	APPROVED
-----	------	-------------	------	----------

.200 DIA.

1		ST. STL. ROD .438 DIA. QQ-S-763C CL.303 COND. A 2010521-50		8030020	
DASH NO		MATERIAL		SPEC.	
MATERIAL SPECIFICATIONS					
QTY REQD	QTY REQD	QTY REQD	QTY REQD	ITEM NO.	CODE IDENT
504	503	502	501		
				PART OR IDENTIFYING NO.	
				NOMENCLATURE OR DESCRIPTION	
				LIST OF MATERIALS	
CONTRACT NO.			RADIO CORPORATION OF AMERICA CAMDEN, N.J.		
COMMODITY CODE 5604			ASTRO ELECTRONIC DIV PRINCETON, N.J.		
DRAWN <i>W. J. J. J. J.</i>			BUSHING, THRUST		
DATE Sept 12-69			FOLDOUT FRAME 2		
CHECKED <i>W. J. J. J. J.</i>					
DATE Oct 15, 69					
DESIGN ACTIVITY APPD. <i>W. J. J. J. J.</i>			CODE IDENT NO.		
DATE 16 Oct 69			SIZE		
			1974052		
			49671 B		
			SCALE 4-1		
			WEIGHT		
			SHEET 1 OF 1		

ES AND
LATING.
IONS
IED
PLACE
ECIMALS
±.005
±.010
±.015
±1/2°
CK TOL

↓ WAS

DASH NO.	MATERIAL	DIMENSIONS (REF)					LUBRICATION
	BARDEN P/N SEE NOTE 1	BORE	O.D.	WIDTH	FLANGE O.D.	FLANGE WIDTH	
1	SR2SSTA5	.1250	.3750	.1562	*	*	SEE NOTE 2
2	SFR2SSTA5	.1250	.3750	.1562	.440	.030	
3	SR2ASSTA5	.1250	.5000	.1719	*	*	
4	SFRI33SSW5	.0937	.1875	.0937	.234	.031	
5	SR133SSW5	.0937	.1875	.0937	*	*	SEE NOTE 2
6	SR3SSW5	.1875	.5000	.1960	*	*	SEE NOTE 4
7	SR4SSW5	.2500	.6250	.1960	*	*	SEE NOTE 4

* WITHOUT FLANGE

NOTES:

1. BEARING MFG BY BARDEN CORP ZOO PARK AVE DANBURY CONNECTICUT.
2. BEARINGS SHALL BE WET VACKOTE LUBRICATED PER BALL BROS RESEARCH CORP PROCESS BPS15-1 USING LUBRICANT 36236. BEARINGS SHALL BE STORED IN SEALED CONTAINERS UNTIL USE.
3. MARK PART NO. RCA 1974400 & APPROPRIATE DASH NO. ON CONTAINERS.
4. LUBRICATE USING G300 SILICON GREASE. GREASE SHALL UNIFORMLY FILL MIN 20% MAX 30% OF THE VOID VOLUME WITHIN THE BEARING. BEARINGS SHALL BE STORED IN SEALED CONTAINERS UNTIL USED.

SEE TABLE
DASH NO.

QTY REQD	QTY REQD	QTY REQD	QTY REQD
504	503	502	501

CONTRACT N

COMMODITY

DRAWN
JG Ham

CHECKED
W. Y. Ham

DESIGN ACT

FOLDOUT PAGE

REPRODUCIBILITY OF THE
ORIGINAL PAGE IS POOR

DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING.		
TOLERANCES ON FINISHED DIMENSIONS UNLESS OTHERWISE SPECIFIED		
BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS
UP TO 6	±.02	±.005
ABOVE 6 TO 24	±.03	±.010
ABOVE 24	±.06	±.015
ANGULAR DIMENSIONS ±1/2°		
SEE RCA PURCH SPEC FOR STOCK TOL		

FIRST MADE FOR	USED ON
NEXT ASS'Y	COLOR CAMERA

ALL EXTERNAL THREADS TO BE CLASS 2A
BEFORE PLATING, AND CLASS 2 AFTER
PLATING. ALL INTERNAL THREADS TO BE
CLASS 2B, UNLESS OTHERWISE SPECIFIED.

WAS

0077261

REVISIONS

SYM	ZONE	DESCRIPTION	DATE	APPROVED
A		ADDED DASH NUMBERS 6 & 7.	9-25-70	J.H. 2550
B		REVISED PER ECN REV. B S.O. 1F5210. R.H.	15-7-71	J. King

CATION

NOTE 2

NOTE 2

NOTE 4

NOTE 4

FOLDOUT PLANE

2

SEE TABLE	SEE NOTE 1 & TABLE	NOTE 2&4	NOTE 2&4
DASH NO.	MATERIAL	FINISH	SPECS.
LIST OF SPECIFICATIONS			

ALTERED PART DWG.

QTY REQD	QTY REQD	QTY REQD	QTY REQD	ITEM NO.	CODE IDENT	PART OR IDENTIFYING NO.	NOMENCLATURE OR DESCRIPTION
504	503	502	501				
CONTRACT NO.					RADIO CORPORATION OF AMERICA CAMDEN, N.J. ASTRO-ELECTRONICS DIV., PRINCETON, N.J.		
COMMODITY CODE 5603					BEARING, LUBRICATED		
DRAWN J.J. Hamann Feb. 27, 1970							
CHECKED W. Lubinski May 6, 1970							
DESIGN ACTIVITY APPD. J. King MAY 7-70							
					CODE IDENT NO.	SIZE	
					49671	B	1974400
					SCALE	WEIGHT	SHEET 1 OF 1

ES AND PLATING.

ENSIONS FIELD

3 PLACE DECIMALS


±.005

±.010

±.015

±1/2°

OCK TOL



NOTES:

1. MATERIAL: OPTICAL CROWN GLASS (C-1)
RETICLE GRADE, NOMINAL INDEX OF 1.523.
2. SURFACES QUALITY SHALL BE 60-40
OR BETTER. FACES SHALL BE FLAT
TO 6 RINGS. FACES SHALL BE
PARALLEL TO 3 MIN/ARC.
3. APPLY ANTI-REFLECTION COATING
TO SURFACES A & B.

				X	
				AR	
				el	
QTY REQD PER DASH NO.					COD IDEN

FOLDOUT FRAME) FOLLOWING PAGE BLANK NOT FILMED

REVISION STATUS WHERE MORE THAN ONE SHEET				THD DATA TO BE INTERPRETED USING NBS HDBK H28 AND MIL-STD-9		UNLESS OTHERWISE SPECIFIED THE SURFACE FINISH OF MACHINED PARTS SHALL NOT EXCEED A MAXIMUM READING 125/PER ANSI STD B46.1 — 1962		UNLESS OTI DIMENSIONS INCLUDE THI			
SH	REV	SH	REV	INTERPRET DIMENSIONS AND TOLERANCES PER ANSI Y14.5-66				TOLE			
								BASIC DIMENSIONS			
								UP TO 6			
				RCA COMMODITY CODE:				ABOVE 6 to 24			
								ABOVE 24			
						NEXT ASSY		USED ON			
						FIRST APPLICATION				ANGULAR D	
										MATERIA	

LTR

SK227322A

REVISIONS

LTR

DESCRIPTION

DATE

APPROVED

SURFACE A

FOLDOUT

		X		8030022	SPEC. WORKMANSHIP		
		AR			SEE NOTE 1		
		1	CODE IDENT	IDENTIFYING NO.	DESCRIPTION	SPECIFICATION	SEE NOTE NO.
ER DASH NO.							

MATERIALS AND SPECIFICATIONS



<p>SPECIFIED OF ALL NOT READING 1962</p>	<p>UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING</p>			<p>CONTRACT NO. NAS-13688</p>	<p>REL</p>	<p>RCA CORPORATION NEW YORK, NY</p>	
	<p>TOLERANCES ON:</p>			<p>DRAWN BY <i>R. Saffo</i> MAY 2, 1974</p>	<p>DATE</p>	<p>ASTRO-ELECTRONICS DIVISION, PRINCETON, N.J. PLANT</p>	
	<p>BASIC DIMENSIONS</p>	<p>2 PLACE DECIMALS</p>	<p>3 PLACE DECIMALS</p>	<p>CHECKED BY <i>M. C. Fuschel</i> May 8, 1974</p>	<p>DATE</p>	<p>COMPENSATING FILTER</p>	
	<p>UP TO 6</p>	<p>± .02</p>	<p>± .010</p>	<p>DESIGN ACTIVITY APPD <i>Bert W. Salter</i> May 9, 1974</p>	<p>DATE</p>	<p>SIZE B</p>	<p>CODE IDENT NO. 49671</p>
	<p>ABOVE 6 to 24</p>	<p>± .03</p>	<p>± .015</p>			<p>SK227322A</p>	
<p>ABOVE 24</p>	<p>± .06</p>	<p>± .020</p>			<p>SCALE 2/1</p>	<p>WEIGHT</p>	<p>SHEET 1 OF 1</p>
<p>ANGULAR DIMENSIONS ± 1/2°</p>							
<p>MATERIAL: SEE TABLE</p>							

TLE.T.V.

D ON

N

RO DIS



SECTION A-A

FOLDOUT /

				AR	
				AR	
				-1	
QTY REQD PER DASH NO.					COD
					IDEN

REVISION STATUS WHERE MORE THAN ONE SHEET				THD DATA TO BE INTERPRETED USING NBS HDBK H28 AND MIL-STD-9		UNLESS OTHERWISE SPECIFIED THE SURFACE FINISH OF MACHINED PARTS SHALL NOT EXCEED A MAXIMUM READING 125/PER ANSI STD B46.1 — 1962		UNLESS OTHER DIMENSIONS INCLUDE THE	
SH	REV	SH	REV	INTERPRET DIMENSIONS AND TOLERANCES PER ANSI Y14.5-66				TOLE	
								BASIC DIMENSIONS	
				RCA COMMODITY CODE:				UP TO 6	
								ABOVE 6 to 24	
								ABOVE 24	
								ANGULAR D	
								MATERIA	

SK2273306

LTR

REVISIONS

LTR

DESCRIPTION

DATE

APPROVED

.270 DIA


.050 $\pm .005$ FOLDOUT ~~TABLE~~

A-A

	AR		1980032-1	PASSIVATE DIP		
	AR		2010521-80	ST. STL ROD .656 DIA.	QQ-S-764a	
	-1	CODE IDENT	IDENTIFYING NO.	DESCRIPTION	SPECIFICATION	SEE NOTE NO.
SER DASH NO.						

MATERIALS AND SPECIFICATIONS

SPECIFIED F L NOT ADING — 1962 LE T.V. ON	UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING			CONTRACT NO. NA59-13688	REL	RCA CORPORATION NEW YORK, NY ASTRO-ELECTRONICS DIVISION, PRINCETON, N.J. PLANT	
	TOLERANCES ON:			DRAWN BY <i>R. Slifko</i>	DATE MAY 21, 1974	BUSHING, THRUST	
	BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS	CHECKED BY <i>David E. Bradley</i>	DATE May 30, 1974		
	UP TO 6	$\pm .02$	$\pm .010$	DESIGN ACTIVITY APPD <i>W. J. Davis</i>	DATE 28 AUG 74		
	ABOVE 6 to 24	$\pm .03$	$\pm .015$	SIZE B	CODE IDENT NO. 49671	SK2273306	
ABOVE 24	$\pm .06$	$\pm .020$	SCALE 4/1	WEIGHT 2.6 GR.	SHEET 1	OF 1	
ANGULAR DIMENSIONS $\pm 1/2^\circ$							
MATERIAL: SEE TABLE							



NOTES:

1. ALL CAPACITORS ARE IN MICROFARADS
2. ALL RESISTORS ARE IN OHMS

FOLDOUT FRAME

REPRODUCIBILITY OF THE
ORIGINAL PAGE IS POOR

QTY REQD PER DASH NO.

COM-
IDENTREVISION STATUS
WHERE MORE THAN
ONE SHEETTHD DATA TO BE INTERPRETED USING
NBS HDBK H28 AND MIL-STD-9UNLESS OTHERWISE SPECIFIED
THE SURFACE FINISH OF
MACHINED PARTS SHALL NOT
EXCEED A MAXIMUM READING
125/PER ANSI STD B46.1 — 1962
✓

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

SH REV SH REV

INTERPRET DIMENSIONS AND
TOLERANCES PER ANSI Y14.5-66

RCA COMMODITY CODE:


NEXT ASSY

USED ON

FIRST APPLICATION

817

REVISIONS			
LTR	DESCRIPTION	DATE	APPROVED




FOLDOUT FRAME

DASH NO.	CONTRACT NO.	IDENTIFYING NO.	DESCRIPTION	SPECIFICATION	NOTE NO.

MATERIALS AND SPECIFICATIONS

UNIFIED NOT DING 1962	DIMENSIONS UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND DECIMALS THEREOF UNLESS PLATING		CONTRACT NO. 49671		RCA CORPORATION NEW YORK, NY ELECTRONICS DIV. PLANT	
	TOLERANCES DIMENSIONS UP TO 6 ± .05 ABOVE 6 ± .01 ALL ± .01		DRAWN BY DATE 4-2-62		AUTOMATIC MOTOR B.D. 1A2	
	SURFACE FINISH UP TO 6 ± .010 ABOVE 6 ± .015 ALL ± .020		CHECKED BY DATE		SIZE B	
	MATERIAL: SEE TABLE		DESIGN ACTIVITY APPD DATE		CODE IDENT NO. 49671	
					SK2273-07	
SCALE — WEIGHT —			SHEET 1 OF			



NOTES:

1. ALL RESISTORS VALUES ARE IN OHMS, $\pm 1\%$
2. ALL CAPACITORS ARE IN MICROFARADS
3. ADJUST R7 FOR 10.0 VOLTS AT E3

FOR YOUR FRAME

REPRODUCIBILITY OF THE
ORIGINAL PAGE IS POOR

[illegible]


REVISION STATUS WHERE MORE THAN ONE SHEET				THD DATA TO BE INTERPRETED USING NBS HDBK H28 AND MIL-STD-9		UNLESS OTHERWISE SPECIFIED THE SURFACE FINISH OF MACHINED PARTS SHALL NOT EXCEED A MAXIMUM READING 125/PER ANSI STD B46.1 -- 1962 ✓		UNLESS OTHERWISE DIMENSIONS ARE IN IN INCLUDE THREADED C	
H	REV	SH	REV	INTERPRET DIMENSIONS AND TOLERANCES PER ANSI Y14.5-66				TOLERANCES	
								UP TO 6	± .02
								ABOVE 6 TO 24	± .03
								ABOVE 24	± .06
				RCA COMMODITY CODE:		NEXT ASSY		USED ON	
						FIRST APPLICATION		ANGULAR DIMENSION	
								MATERIAL: SEE	

817

REVISIONS

LTR	DESCRIPTION	DATE	APPROVED
-----	-------------	------	----------

N1490





HOLDOUT

DASH NO.	CODE IDENT	IDENTIFYING NO.	DESCRIPTION	SPECIFICATION	SEE NOTE NO.

MATERIALS AND SPECIFICATIONS

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING	CONTRACT NO.		REL	RCA CORPORATION - NEW YORK, NY	
	DRAWN BY		DATE	ELECTRONICS DIV. PRINCIPAL MFG PLANT	
	CHECKED BY		DATE	SK 2273-409	
	DESIGN ACTIVITY APPD		DATE	SIZE	CODE IDENT NO.
	MATERIAL: SEE TABLE			B	49671
TOLERANCES ON:		SHEET 1 OF 1			
EXTR DIMENSIONS	FORMAL DIMENSIONS	FINISH DIMENSIONS			
UP TO 6	± .02	± .010			
ADDED	± .03	± .015			
ADDED 24	± .06	± .020			
ANGULAR DIMENSIONS ± 1/2°					
SCALE		WEIGHT			



SECTION A-A

NOTES:

1. MATERIAL - CRES (TYPE 303) BAR .281 DIA
QQ-S-764 a (2010521-30).
2. PRESS FIT ITEM 2 INTO ITEM 1.
3. WORKMANSHIP SHALL BE IN ACCORDANCE
WITH PARTS LIST, ITEM 3.
4. TAG OR BAG PART NO. 49671-SK2277717-501
PER MIL-STD-130.
5. ALTER ITEM 1 AS SHOWN.


REPRODUCIBILITY OF THE
ORIGINAL PAGE IS POOR

FOLDOUT FRAME

[illegible]

UNLESS OTHERWISE SPECIFIED THE SURFACE FINISH OF MACHINED PARTS SHALL NOT EXCEED A MAXIMUM READING 125 PER ANSI STD B46.1 — 1962	UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING			CONTRACT NAS9
	TOLERANCES ON:			DRAWN <i>[Signature]</i>
	BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS	CHECKED <i>[Signature]</i>
	UP TO 6 ABOVE 6 TO 24 ABOVE 24	$\pm .02$ $\pm .1$ $\pm .06$	$\pm .010$ $\pm .015$ $\pm .020$	DESIGN A <i>[Signature]</i>
INTERPRET DIMENSIONS AND TOLERANCES PER ANSI Y14.5-66			ANGULAR DIMENSIONS $\pm \frac{1}{4}^\circ$	
THD DATA TO BE INTERPRETED USING NBS HDBK H28 AND MIL-STD-9			SK22270979 SHUTTLE T.V.	
NEXT ASSY	USED ON	RCA COMMODITY CODE:		
FIRST APPLICATION			[Blank]	

REVISIONS				
ZONE	LTR	DESCRIPTION	DATE	APPROVED



FOLDSOUT FRAME 3


SECTION A-A

FOR PARTS LIST SEE PL SK 227717

[illegible]

MATERIALS AND SPECIFICATIONS

UNLESS OTHERWISE SPECIFIED THE SURFACE FINISH OF MACHINED PARTS SHALL NOT EXCEED A MAXIMUM READING 125 PER ANSI STD B46.1 — 1962	UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING		CONTRACT NO. NAS9-13688		REL		RCA CORPORATION 1 NEW YORK, NY		
	TOLERANCES ON:		DRAWN <i>R. [Signature]</i> APR 19, 1974		DATE		ASTRO-ELECTRONICS DIVISION, PRINCETON, N.J.		
	BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS	CHECKED <i>[Signature]</i> May 30, 1974		DATE		GEAR	
	UP TO 6 ABOVE 6 TO 24 ABOVE 24	$\pm .02$ $\pm .03$ $\pm .05$	$\pm .010$ $\pm .015$ $\pm .020$	DESIGN ACTIVITY APPD. <i>[Signature]</i>		DATE <i>[Signature]</i>		SIZE C	CODE IDENT NO. 49671
INTERPRET DIMENSIONS AND TOLERANCES PER ANSI Y14.5-66	THD DATA TO BE INTERPRETED USING NBS HDBK H28 AND MIL-STD-9		ANGULAR DIMENSIONS $\pm 1/2^\circ$		SCALE 4/1		WEIGHT	SHEET 1 OF 1	
SK2279979	SHUTTLE TV		RCA COMMODITY CODE:		C		SK2277717		
NEXT ASSY	USED ON								
FIRST APPLICATION									

PARTS LIST		 RCA CORPORATION NEW YORK, NY		REVISION DATE	PLSK2277717	REV LTR
		ASTRO-ELECTRONICS DIVISION, PRINCETON, N.J.				
LIST TITLE: GEAR		PREPARED BY <i>R. Sijko</i> MAY 18, 1974		REL.	CODE IDENT NO. 49671	SHEET OF 2
		CHECKED BY <i>James E. Goodrich</i> May 30, 1974				1 SHEETS
		DESIGN ACTIVITY APP'D <i>Bert M. Saltz</i> May 30, 74			CONTRACT NO.	NAS9-13688

REVISIONS

LTR	DESCRIPTION	DATE	APPROVED	LTR	DESCRIPTION	DATE	APPROVED

INTERPRET SYMBOLS USED AS FOLLOWS:

UNITS OF MEASURE (UM)	QUANTITIES	SYMBOL
A — Inches H — Barrels T — Each	X — Applicable document	U — Govt or customer furnished * — Vendor item, See specification or source control drawing.
B — Feet J — Pounds		
C — Yards L — Pair	O — For ref only	K — Govt or customer furnished and installed
D — Ounces M — Set		
E — Pints N — Kit		
F — Quarts P — Roll		
G — Gallons R — Box, Case		

[illegible]

UNLESS OTHERWISE SPECIFIED THE SURFACE FINISH OF MACHINED PARTS SHALL NOT EXCEED A MAXIMUM READING 125 PER ANSI STD B46.1 — 1962		UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING		CONTRACT NO. N459-13688		REL		RCA		RCA CORPORATION NEW YORK, NY	
				DRAWN L. Seppa APR 22, 1974		DATE		ASTRO-ELECTRONICS DIVISION, PRINCETON, N.J.		PLANT	
INTERPRET DIMENSIONS AND TOLERANCES PER ANSI Y14.5-66		TOLERANCES ON:		CHECKED May 30, 1974		DATE		SHAFT, COLOR WHEEL			
		BASIC DIMENSIONS		2 PLACE DECIMALS		3 PLACE DECIMALS					
THD DATA TO BE INTERPRETED USING NBS HDBK H28 AND MIL-STD-9		UP TO 6		± .02		± .010		SIZE C			
		6 TO 24		± .03		± .015					
NEXT ASSY		ABOVE 24		± .06		± .020		CODE IDENT NO.		SK2277718	
		FIRST APPLICATION		RCA COMMODITY CODE:		DESIGN ACTIVITY APPD. APR 28 1974		DATE		SHEET 1 OF 1	

cu

B



A

HOUDOUT ~~REDACTED~~


QTY REQD PER DASH NO.	IDENT
1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10
11	11
12	12
13	13
14	14
15	15
16	16
17	17
18	18
19	19
20	20
21	21
22	22
23	23
24	24
25	25
26	26
27	27
28	28
29	29
30	30
31	31
32	32
33	33
34	34
35	35
36	36
37	37
38	38
39	39
40	40
41	41
42	42
43	43
44	44
45	45
46	46
47	47
48	48
49	49
50	50
51	51
52	52
53	53
54	54
55	55
56	56
57	57
58	58
59	59
60	60
61	61
62	62
63	63
64	64
65	65
66	66
67	67
68	68
69	69
70	70
71	71
72	72
73	73
74	74
75	75
76	76
77	77
78	78
79	79
80	80
81	81
82	82
83	83
84	84
85	85
86	86
87	87
88	88
89	89
90	90
91	91
92	92
93	93
94	94
95	95
96	96
97	97
98	98
99	99
100	100

FIRST APPLICATION

RCA COMMODITY CODE:

1


- 2B




FOLDOUT ~~CHARTER~~ 2

				X	8030022	SPEC. WORKMANSHIP		
				AR	1980032-1	PASSIVATING DIP		
				AR	2010462-232	CRES (TYPE 302) PLATE .50 THK	QQ-S-766C(5)	
				-I				
QTY REQD PER DASH NO.				CODE IDENT	IDENTIFYING NO.	DESCRIPTION	SPECIFICATION	SEE NOTE NO.


MATERIALS AND SPECIFICATIONS

UNLESS OTHERWISE SPECIFIED THE SURFACE FINISH OF MACHINED PARTS SHALL NOT EXCEED A MAXIMUM READING 125/PER ANSI STD B46.1 — 1962	UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING			CONTRACT NO. NAS9-13688	REL _____			RCA CORPORATION - NEW YORK, NY	
	TOLERANCES ON:			DRAWN <i>R. Slifko</i>	DATE APR. 23, 1974	ASTRO-ELECTRONICS DIVISION, PRINCETON, N.J. PLANT			
	BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS	CHECKED _____	DATE _____	<div style="text-align: center; font-size: 2em; font-weight: bold;">CLAMP</div>			
	UP TO 6 ± .02 6 TO 24 ± .03 ABOVE 24 ± .06	_____ _____ _____	± .010 ± .015 ± .020						
INTERPRET DIMENSIONS AND TOLERANCES PER ANSI Y 4.5-66	ANGULAR DIMENSIONS ± 1/2°			DESIGN ACTIVITY APPD. <i>W. J. [Signature]</i>	DATE FEB 1974	SIZE C	CODE IDENT NO. 49671	SK2277722	
THD DATA TO BE INTERPRETED USING N8 - HDBK H28 AND MIL-STD-9	RCA COMMODITY CODE:			_____		SCALE 4/1 WEIGHT _____ SHEET 1 OF 1			
SK2277722 SHUTTLE T.V.	_____			_____		_____			
NEXT ASSY USED ON	_____			_____		_____			
FIRST APPLICATION	_____			_____		_____			



RCA 2419-3 (4-71) 7074

REVISIONS			
ZONE	LTR	DESCRIPTION	DATE
			APPROVED



SECTION A-A

HOLDOUT DRAWING

7726-1

			X		8030022	SPEC. WORKMANSHIP			
			AR		1980039-1	BLACK ANODIZE		MIL-A-8625	
			AR		2010637-200	AL ALY BAR 2024-T4 235E-A		QQ-A-225/6c	
			-1	CODE IDENT	IDENTIFYING NO.	DESCRIPTION	SPECIFICATION	SEE NOTE NO.	
QTY REQD PER DASH NO.									

MATERIALS AND SPECIFICATIONS

UNLESS OTHERWISE SPECIFIED THE SURFACE FINISH OF MACHINED PARTS SHALL NOT EXCEED A MAXIMUM READING $\sqrt{125}$ PER ANSI STD B46.1 — 1962		UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING		CONTRACT NO. NAS 9-13688		REL		ECA CORPORATION NEW YORK, NY	
INTERPRET DIMENSIONS AND TOLERANCES PER ANSI Y14.5-66		TOLERANCES ON: BASIC DIMENSIONS UP TO 6 $\pm .02$ ABOVE 6 TO 24 $\pm .03$ ABOVE 24 $\pm .06$		DRAWN R. Sifbo APR 25, 1974		DATE		ASTRO-ELECTRONICS DIVISION, PRINCETON, N.J.	
THD DATA TO BE INTERPRETED USING NBS HDBK H28 AND MIL-STD-9		ANGULAR DIMENSIONS $\pm \frac{1}{2}^\circ$		CHECKED E. Bordley May 30, 1974		DATE		RETAINER-LENS	
SK2277779 SHUTTLE T.V.		RCA COMMODITY CODE:		DESIGN ACTIVITY APPD.		DATE		SIZE CODE IDENT NO.	
NEXT ASSY USED ON		FIRST APPLICATION		SCALE 2/1		WEIGHT		SK2277726	
								SHEET 1 OF 1	

Technical drawing of a circular part, likely a flange or end view of a pipe. The drawing shows a circular cross-section with a central hole. The outer diameter is dimensioned as 216 DIA. The inner diameter is dimensioned as 173.8 DIA. There are four small circles, each with a crosshair, located at the top, bottom, left, and right positions, representing bolt holes. A leader line points to one of these bolt holes.

1. TAG OR BAG PART NO. 49671-SK2277728-1
PER MIL-STD-130.

FOLDOUT FRAME

				X			E
				AR			17
				-1			
QTY REQD PER DASH NO.						CODE IDENT	

UNLESS OTHERWISE SPECIFIED
THE SURFACE FINISH OF
MACHINED PARTS SHALL NOT
EXCEED A MAXIMUM READING
125/PER ANSI STD B46.1 — 1952

INTERPRET DIMENSIONS AND TOLERANCES PER ANSI Y14.5-66

THE DATA TO BE INTERPRETED
USING NBS HDBK H2B AND
MIL-STD-9

SK2279979 SHUTTLE TV.

NEXT ASSY

USED ON

FIRST APPLICATION


UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND
INCLUDE THICKNESS OF PLATING

TOLERANCES ON:


BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS
UP TO 6	± .02	± .010
ABOVE 6 TO 24	± .03	± .015
ABOVE 24	± .06	± .020

ANGULAR DIMENSIONS - 1/3"

RCA COMMODITY CODE:



2.16 DIA



.032 (REF)

FOLDOUT SHEET

2

7728-1


			X		8030022	SPEC. WORKMANSHIP			
			AR		1721943-211	AL ALY LAM. SHIM .032 THK	QQ-A-561		
			-1						
QTY REQD PER DASH NO.				CODE IDENT	IDENTIFYING NO.	DESCRIPTION	SPECIFICATION	SEE NOTE NO.	

MATERIALS AND SPECIFICATIONS

<p>UNLESS OTHERWISE SPECIFIED THE SURFACE FINISH OF MACHINED PARTS SHALL NOT EXCEED A MAXIMUM READING $\frac{125}{\sqrt{R}}$ PER ANSI STD B46.1 — 1962</p> <p>INTERPRET DIMENSIONS AND TOLERANCES PER ANSI Y14.5-66</p> <p>THIS DATA TO BE INTERPRETED USING NBS HDBK H28 AND RAL-STD-9</p> <p>SK2279979 SHUTTLE T.V.</p> <p>NEXT ASSY USED ON FIRST APPLICATION</p>		<p>UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING</p> <p>TOLERANCES ON:</p> <table><tr><td>BASIC DIMENSIONS</td><td>2 PLACE DECIMALS</td><td>3 PLACE DECIMALS</td></tr><tr><td>UP TO 6</td><td>$\pm .02$</td><td>$\pm .010$</td></tr><tr><td>6 TO 24</td><td>$\pm .03$</td><td>$\pm .015$</td></tr><tr><td>ABOVE 24</td><td>$\pm .06$</td><td>$\pm .020$</td></tr></table> <p>ANGULAR DIMENSIONS $\pm \frac{1}{2}^\circ$</p> <p>RCA COMMODITY CODE:</p>		BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS	UP TO 6	$\pm .02$	$\pm .010$	6 TO 24	$\pm .03$	$\pm .015$	ABOVE 24	$\pm .06$	$\pm .020$	CONTRACT NO. NAS9-13688		REL	RCA		RCA CORPORATION - NEW YORK, NY	
BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS																				
UP TO 6	$\pm .02$	$\pm .010$																				
6 TO 24	$\pm .03$	$\pm .015$																				
ABOVE 24	$\pm .06$	$\pm .020$																				
DRAWN <i>R. S. S. Apr. 25, 1974</i>		DATE	ASTRO-ELECTRONICS DIVISION, PRINCETON, N.J. PLANT																			
CHECKED <i>May 30, 1974</i>		DATE	SHIM, LENS-RETAINER																			
DESIGN ACTIVITY APPD. <i>May 17</i>		DATE	SIZE C	CODE IDENT NO. 49671	SK2277728																	
		SCALE 2/1							WEIGHT	SHEET 1 OF 1												

- 2 MM

SURFACE A



DASH No.	OPTICAL DENSITY VALUE
1	0
2	.1 ± .025
3	.2 ± .025
4	.3 ± .025
5	.4 ± .025
6	.5 ± .025


NOTE

1. MATERIAL: OPTICAL GLASS RETICLE GRADE. SURFACES QUALITY SHALL BE 60-40 OR BETTER. FACES SHALL BE FLAT TO 6 RINGS, FACES SHALL BE PARALLEL TO 3 MIN/ARC.
2. INCONEL NEUTRAL DENSITY COATINGS SHALL BE APPLIED TO SURFACE A, PROVIDING FILTER DENSITIES AS TABULATED.

				X		803
				AR		
				-1	CODE IDENT	IDENT
QTY REQD PER DASH NO						

REPRODUCIBILITY OF THE
ORIGINAL PAGE IS POOR

UNLESS OTHERWISE SPECIFIED THE SURFACE FINISH OF MACHINED PARTS SHALL NOT EXCEED A MAXIMUM READING $1\frac{1}{2}$ PER ANSI STD B46.1 — 1962 ✓	UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING		
	TOLERANCES ON		
	BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS
INTERPRET DIMENSIONS AND TOLERANCES PER ANSI Y14.5 66	UP TO 6	• .02	• .010
THIS DATA TO BE INTERPRETED USING NBS HDBK H2E AND MIL-STD-9	ADDITIONAL 6 TO 24	• .03	• .015
	ABOVE 24	• .05	• .020
		ANGULAR DIMENSIONS • 1°	
	SHUTTLE		
NEXT ASSY	USED ON		
FIRST APPLICATION			
RCA COMMODITY CODE			



FOLIOLE REACT



ALL BE
ER

				X		8030022	SPEC. WORKMANSHIP			
				AR			SEE NOTE 1			
				-1						
QTY REQD PER DASH NO					CODE IDENT	IDENTIFYING NO.	DESCRIPTION	SPECIFICATION	SEE NOTE NO.	

MATERIALS AND SPECIFICATIONS

UNLESS OTHERWISE SPECIFIED THE SURFACE FINISH OF MACHINED PARTS SHALL NOT EXCEED A MAXIMUM READING 125 PER ANSI STD B46.1 — 1962		UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING		CONTRACT NO. NAS9-13682		REL.		RCA CORPORATION - NEW YORK, NY	
INTERPRET DIMENSIONS AND TOLERANCES PER ANSI Y14.5 G6		TOLERANCES ON		DRAWN <i>R. Sefter</i> MAY 30, 1974		DATE		ASTRO-ELECTRONICS DIV, PRINCETON, N.J. PLANT	
		BASIC DIMENSIONS		2 PLACE DECIMALS		3 PLACE DECIMALS		CHECKED <i>M. C. Knecht</i> May 8, 1974	
TYP DATA TO BE INTERPRETED USING NAS HDBK H2B AND MIL STD 9		UP TO 6		- .02		+ .010		FILTER SEGMENT, NEUTRAL DENSITY	
		ABOVE 6 TO 24		- .03		+ .015			
		ABOVE 24		- .06		+ .020			
		ANGULAR DIMENSIONS		- 1/2		DESIGN ACTIVITY APPD.		DATE	
SHUTTLE		RCA COMMODITY CODE		C		SIZE		CODE IDENT NO	
NEXT ASSY		USED ON		Bert M. Saltoff May 7, 1974		C		49671	
FIRST APPLICATION						SCALE		NONE	
						WEIGHT		SHEET 1 OF 1	

- 2MM



1. MATERIAL: OPTICAL GLASS RETICLE GRADE. SURFACES QUALITY SHALL BE 60-40 OR BETTER. FACES SHALL BE FLAT TO 6 RINGS, FACES SHALL BE PARALLEL TO 3 MIN/ARC.

GLASS SHALL BE SIMILAR TO SCHOTT OG590
HAVING SPECTRAL CHARACTERISTICS AS
SHOWN ON GRAPH, WAVELENGTH FOR 50%
TRANSMISSION POINT SHALL BE $590 \pm 10 \text{ NM}$

				X		803
				AR		
				-1		
QTY REQD PER DASH NO.					CODE IDENT	IDENTI


ROLL-OUT

UNLESS OTHERWISE SPECIFIED THE SURFACE FINISH OF MACHINED PARTS SHALL NOT EXCEED A MAXIMUM READING 175 PER ANSI STD B46.1 — 1962	UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING			CON NA DRAW
	TOLERANCES ON:			CHEE DESI
	BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS	
	UP TO 6	± .02	± .010	
INTERPRET DIMENSIONS AND TOLERANCES PER ANSI Y14.5-66	ABOVE 6 TO 24	± .03	± .015	
	ABOVE 24	± .06	± .020	
	ANGULAR DIMENSIONS ± 1/2			
	SHUTTLETV			
NEXT ASSY	USED ON	RCA COMMODITY CODE.		
FIRST APPLICATION				

2MM

1.110R

-.0828





FOLDOUT DRAWING

SEE
NOTE
NO.

PLANT

SHEET 1 OF 1




1. MATERIAL: OPTICAL GLASS RETICLE GRADE. SURFACES QUALITY SHALL BE 60-40 OR BETTER. FACES SHALL BE FLAT TO 6 RINGS, FACES SHALL BE PARALLEL TO 3 MIN/ARC.

2. SURFACE "A" SHALL HAVE AN INTERFERENCE COATING SIMILAR TO FISH-SCHURMAN ML495C, HAVING SPECTRAL CHARACTERISTICS AS SHOWN. MAX. AND MIN. WAVELENGTHS FOR 50% TRANSMISSION POINTS SHALL BE,

400 NM \pm 10 NM
480 NM \pm 10 NM

			X			80306
			AR			
			-1			
QTY REQD PER DASH NO.				CODE IDENT	IDENTIFYING	

RCA 2419-3 (4-71) 7074



1. MATERIAL: OPTICAL GLASS RETICLE GRADE. SURFACES QUALITY SHALL BE 60-400R BETTER. FACES SHALL BE FLAT TO 6 RINGS, FACES SHALL BE PARALLEL TO 3 MIN/ARC. GLASS SHALL BE SIMILAR TO SCHOTT OG515 HAVING SPECTRAL CHARACTERISTICS AS SHOWN ON GRAPH. SURFACE "A" SHALL HAVE AN INTERFERENCE COATING SIMILAR TO FISH-SCHURMAN ML 580NM, HAVING SPECTRAL CHARACTERISTICS AS SHOWN. MAX. AND MIN. WAVELENGTHS FOR 50% TRANSMISSION POINTS SHALL BE:

UNLESS OTHERWISE SPECIFIED
THE SURFACE FINISH SHALL NOT EXCEED A MAX. R.A. OF 125 PER ANSI

				X		8030	
				AR			
				-1			
QTY REQD PER DASH NO.					CODE IDENT	IDENTIF	

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING		
TOLERANCES ON:		
BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS
UP TO 6	± .02	± .010 ± .015 + .020
ABOVE 6 TO 24	± .03	
ABOVE 24	± .05	
ANGULAR DIMENSIONS		+ 1/2


CONT	NA
DRAW	
CHECK	W
DESIG	Be

-140R

1.1103

-077R

-0328



FOLD-OUT FRAMES

MADE.
FOR
6
TO

OG515
AS
HAVE
TO

UNLESS OTHERWISE SPECIFIED
THE SURFACE FINISH OF
MACHINED PARTS SHALL NOT
EXCEED A MAXIMUM READING
125/PER ANSI STD B46.1 — 1962

INTERPRET DIMENSIONS AND
TOLERANCES PER ANSI Y14.5-66

THE DATA TO BE INTERPRETED
USING NBS HDBK H28 AND
MIL-STD-9

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND
INCLUDE THICKNESS OF PLATING

TOLERANCES ON

BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS
UP TO 6	± .02	± .010
6 TO 24	± .03	± .015
ABOVE 24	± .05	± .020

ANGULAR DIMENSIONS • 1/4

CONTRACT NO.
NAS9-13688

DRAWN *R. Sefko* DATE *APR 30, 1974*

CHECKED: *M. C. Busch* DATE: *May 8, 1974*

DESIGN ACTIVITY APPD. DATE

REAL

RCA CORPORATION NEW YORK, NY

ASTRO-ELECTRONICS DIVISION, PRINCETON, N.J. PLANT


FILTER SEGMENT,
GREEN

SIZE	CODE IDENT NO.	
C	49671	SK2277734

SCALE NONE	WEIGHT
------------	--------

SHEET 1 OF 1

RCA COMMODITY CODE:



NOTES:


1. MATERIAL: SCHOTT HALL FILTER GLASS
2. SURFACES QUALITY SHALL BE 60-40 OR BETTER, FACES SHALL BE FLAT TO GRINGS, FACES SHALL BE PARALLEL TO 3 MIN/ARC.
3. SURFACE "A" SHALL HAVE AN INTERFERENCE COATING SIMILAR TO FISH-SCHURMAN ML3025S (8/18/71).
4. RESULTANT FILTER SHALL HAVE NOMINAL TRANSMISSION FROM 415 TO 550 NM OF $85\% \pm 4\%$ THE 50% TRANSMISSION POINTS SHALL BE.
 $380 \text{ NM} \pm 10 \text{ NM}$
 $645 \text{ NM} \pm 10 \text{ NM}$

FOLDOUT

				X			8030022
				AR			
				-1			
QTY REQD PER DASH NO.					CODE IDENT	IDENTIFYING NO.	

UNLESS OTHERWISE SPECIFIED THE SURFACE FINISH OF MACHINED PARTS SHALL NOT EXCEED A MAXIMUM READING 125/√R PER ANSI STD B46.1 — 1962	UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING			CONTRACT NO. NAS9-13
	TOLERANCES ON:			DRAWN R. S. Miller
	BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS	CHECKED C. E. Schuch
	UP TO 6	± .02	± .010	
INTERPRET. DIMENSIONS AND TOLERANCES PER ANSI Y14.5-66	6 TO 24 <small>ADDED</small>	± .03	± .015	
THD DATA TO BE INTERPRETED USING NBS HDBK H28 AND MIL-STD-9	ABOVE 24	± .06	± .020	
ANGULAR DIMENSIONS ± 1/2°				DESIGN ACTIVITY Bentley & Co.
	SHUTTLE TV			
NEXT ASSY	USED ON			
FIRST APPLICATION				
RCA COMMODITY CODE:				

REVISIONS			
ZONE	LTR	DESCRIPTION	DATE




FOLDOUT PLATE

				X		8030022	SPEC. WORKMANSHIP		
				AR		1980032-1	PASSIVATING DIP		
				AR		2010556-250	CRES (TYPE 304) SHT. 250TH QQ-S-766c(5)		
				-1	CODE IDENT	IDENTIFYING NO.	DESCRIPTION	SPECIFICATION	SEE NOTE NO.
QTY REQD PER DASH NO.									

MATERIALS AND SPECIFICATIONS

UNLESS OTHERWISE SPECIFIED THE SURF. FIN. OF MACHINED PARTS SHALL NOT EXCEED A MAX READING OF 125 PER USAS B46.1-1962		UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING TOLERANCES ON: <table border="1"> <tr> <th>BASIC DIMENSIONS</th> <th>2 PLACE DECIMALS</th> <th>3 PLACE DECIMALS</th> </tr> <tr> <td>UP TO 6</td> <td>± .02</td> <td>± .010</td> </tr> <tr> <td>ABOVE 6 TO 24</td> <td>± .03</td> <td>± .015</td> </tr> <tr> <td>ABOVE 24</td> <td>± .06</td> <td>± .020</td> </tr> </table> ANGULAR DIMENSIONS ± 1/2°		BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS	UP TO 6	± .02	± .010	ABOVE 6 TO 24	± .03	± .015	ABOVE 24	± .06	± .020	CONTRACT NO. NAS9-15688 DRAWN <i>R. S. S. MAY 15, 1974</i> CHECKED <i>E. Goodley May 30, 1974</i> DESIGN ACTIVITY APPD. <i>W. S. S. 28 May 74</i>		RCA CORPORATION NEW YORK, NY ASTRO-ELECTRONICS DIVISION, PRINCETON, N.J.	
BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS																	
UP TO 6	± .02	± .010																	
ABOVE 6 TO 24	± .03	± .015																	
ABOVE 24	± .06	± .020																	
DIMENSIONS AND TOLERANCES PER USAS Y145-88 THD DATA TO BE INTERPRETED USING HANDBK H28 AND MIL-STD 9				PLATE, SENSOR MOUNTING															
SK2279979 SHUTTLE T.V. NEXT ASSY USED ON FIRST APPLICATION		RCA COMMODITY CODE:		SIZE C CODE IDENT NO. 49671 SCALE 4/1 WEIGHT SHEET 1 OF 1															



NOTES:

1. U1 & U8 ARE TYPE CD4011AE
2. U2, U4, U5, U6, U11 ARE TYPE CD4027AE
3. U3 IS TYPE CD4023AE
4. U7 & U9 ARE TYPE CD4018AE
5. U10 IS TYPE CD4046AE
6. U12 IS TYPE CD4050AE
7. ALL CAPACITORS ARE IN MICROFARADS UNLESS OTHERWISE STATED
8. ALL RESISTOR ARE IN OHMS UNLESS OTHERWISE STATED

FOLDOUT PART

UNLESS OTHERWISE SPECIFIED
THE SURFACE FINISH OF
MACHINED PARTS SHALL NOT
EXCEED A MAXIMUM READING
125 PER ANSI STD B46.1 — 1962

INTERPRET DIMENSIONS AND
TOLERANCES PER ANSI Y14.5-66

THD DATA TO BE INTERPRETED
USING NBS HDBK H28 AND
MIL-STD-9

NEXT ASSY
USED ON
FIRST APPLICATION


UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND
INCLUDE THICKNESS OF PLATING

TOLERANCES ON:


BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS
UP TO 6	± .02	± .010
ABOVE 6 TO 24	± .03	± .015
ABOVE 24	± .06	± .020

ANGULAR DIMENSIONS ± 1/2 °

RCA COMMODITY CODE:



REPRODUCIBILITY OF THE
AT PAGE IS POOR



NOTES:

1. UNLESS OTHERWISE SPECIFIED: ALL RESISTOR VALUES ARE IN OHMS, 1/4 WATT, $\pm 5\%$
2. UNLESS OTHERWISE SPECIFIED: ALL CAPACITOR VALUES ARE IN MICROFARADS
3. ALL DIODES ARE TYPE 1N645
4. Q1, Q2, Q4, Q6, Q7, Q8, Q9, Q12 ARE TYPE 2N2907A
5. Q3, Q5, Q10, Q11 ARE TYPE 2N2222A
6. U1 IS TYPE CD4027AE
7. U2, U3, U4, ARE TYPE CD4011AE
8. U5, U6 ARE TYPE CD4023AE
9. U7 IS TYPE CD4050AE

UNLESS OTHERWISE SPECIFIED
THE SURFACE FINISH OF
MACHINED PARTS SHALL NOT
EXCEED A MAXIMUM READING
125 PER ANSI STD B46.1 — 1962

INTERPR. DIMENSIONS AND
TOLERANCES PER ANSI Y14.5-66

THD DATA TO BE INTERPRETED
USING NBS HDBK H28 AND
MIL-STD-9


NEXT ASSY USED ON
FIRST APPLICATION

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES AND
INCLUDE THICKNESS OF PLATING

TOLERANCES ON:		
BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS
UP TO 6	$\pm .02$	$\pm .010$
6 TO 24	$\pm .03$	$\pm .015$
ABOVE 24	$\pm .06$	$\pm .020$
ANGULAR DIMENSIONS $\pm 1/2^\circ$		

RCA COMMODITY CODE:

DESCRIPTION	DATE	APPROVED
A ADDED Q7 R31 DESIGNATION; CHANGED VALUE OF C1 FROM 10 TO 8;	9-6-74	J. Hulet



I.C.	510.0 V	GROUND
U1	16	8
U2	14	7
U3	14	7
U4	14	7
U5	14	7
U6	14	7
U7	1	8

[illegible]

UNLESS OTHERWISE SPECIFIED THE SURFACE FINISH OF MACHINED PARTS SHALL NOT EXCEED A MAXIMUM READING ✓ .015 PER ANSI STD B46.1 — 1962	TOLERANCES ARE IN INCHES AND INCLUDE THICKNESS OF PLATING		CONTRACT NO. NAS 9-13688		REL.	RCA CORPORATION NEW YORK, NY
	TOLERANCES ON:		DRAWN <i>Schmitt-Hall</i>	DATE 5-9-74	ASTRO ELECTRONICS DIV. PRINCETON, N.J. PLANT	
	BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS	CHECKED	DATE	SCHEMATIC STEPPER MOTOR LOGIC & DRIVER BD. 2A3, 2A4, 2A5
	UP TO 6	± .02	± .010			
	Above 6 TO 24	± .03	± .015			
	Above 24	± .06	± .020			
	ANGULAR DIMENSIONS ± ½ °					
RCA COMMODITY CODE:					C 49671 SK2277776	
NEXT ASSY USED ON FIRST APPLICATION					SCALE WEIGHT SHEET 1 OF 1	

6 CUTOUT PATTERNS EQUALLY SPACED 60°

12 SEE NOTE

SEE DETAIL A

6" $\pm \frac{1}{4}$ "

B

1.150 R

337R

1000R

180" $\pm \frac{1}{4}$ "


REF ROTATION

3 SEE NOTES 3 & 4

-

SECTION

FOXBORNE 100-10000




FOLDOUT PAGE

FOR PARTS LIST SEE PL SK127005B

QTY PER CASH NO.	CODE CLASS	CONTAINER NO.	DESCRIPTION	WARRANTY INFO	QTY UNIT
MATERIALS USED - PRESTRESS					

[illegible]

PARTS LIST				RCA CORPORATION NEW YORK, NY		REVISION DATE		PLSK2279958		REV LTR	
		ASTRO-ELECTRONICS DIVISION, PRINCETON, N.J									
LIST TITLE: WHEEL, FILTER				PREPARED BY <i>A. J. Slikko</i> MAY 17, 1974		DATE		GEL		CODE IDENT NO. 49671	
				CHECKED BY		DATE				SHEET 1 OF 2 SHEETS	
				DESIGN ACTIVITY APPD <i>Bentzen Soltoff</i> May 17, 1974		DATE				CONTRACT NO. NAS-9-13688	

REVISIONS

LTR	DESCRIPTION	DATE	APPROVED	LTR	DESCRIPTION	DATE	APPROVED

INTERPRET SYMBOLS USED AS FOLLOWS:

UNITS OF MEASURE (UM)			QUANTITIES	SYMBOL	
A — Inches	H — Barrels	T — Each	X — Applicable document	U — Govt or customer furnished	* — Vendor item, See specification or source control drawing.
B — Feet	J — Pounds				
C — Yards	L — Pair				
D — Ounces	M — Set		O — For ref only	K — Govt or customer furnished and installed	
E — Pints	N — Kit				
F — Quarts	P — Roll				
G — Gallons	R — Box, Case				

FREE!
Astro Electronics

Project SHUTTLE IV
Prepared by R. SLIFKOP Date APR 29, 1974
Checked by _____ Date _____

[illegible]

PARTS LIST

INCOAT

RCA CORPORATION | NEW YORK, NY

REVISION
DATE

PLSK2279971

REV
LTR

ASTRO-ELECTRONICS DIVISION, PRINCETON, N.J.

LIST TITLE:

GEAR HOUSING, FRONT

PREPARED BY

R. Slyko MAY 6, 1974

DATE

REL

CODE IDENT NO.

49671

SHEET
OF 21
SHEETS

CHECKED BY

David E. Bondage May 30, 1974

DATE

DESIGN ACTIVITY APPR

Benton Saltoff May 30, 1974

DATE

CONTRACT NO.

NAS9-13688


REVISIONS

LTR	DESCRIPTION	DATE	APPROVED	LTR	DESCRIPTION	DATE	APPROVED

INTERPRET SYMBOLS USED AS FOLLOWS:

UNITS OF MEASURE (UM)	QUANTITIES	SYMBOL
A — Inches B — Feet C — Yards D — Ounces E — Pints F — Quarts G — Gallons	H — Barrels J — Pounds L — Pair M — Set N — Kit P — Roll R — Box, Case	T — Each X — Applicable document O — For ref only U — Govt or customer furnished K — Govt or customer furnished and installed * — Vendor item, See specification or source control drawing.

[illegible]






SEE NOTE 7

- DRILL, CSK., TAP & INSTALL
ITEM 3 PER ITEM 5
6 HOLES EQ SPACED
ON 1.93 DIA B.C.

DRILL, CSK, TAP & INSTALL
ITEM 3 PER ITEM 15
3 PLACES AS SHOWN
ON 1, 3, 10 & B.C.

DRILL, CSK., TAPE INSTALL
ITEM 4 PER ITEM 5
TYP THREE PLACES



SECTION A A

SECTION B-B




NOTES:

1. MATERIAL - ALUM ALLOY 2024-T4 QQ-A-250/4C
750 THK (49671-2010686-595)
2. DRILL .0521" DIA HOLE FOR ITEM 2.
3. PRESS FIT ITEM 2 INTO ITEM 1. SEAT FLUSH
WITH .460 DIA CROCK SURFACE.
4. FINISH- BLACK ANODIZE 1980043-1.
5. WORKMANSHIP SHALL BE IN ACCORDANCE WITH
PARTS LIST, ITEM 5.
6. TAG OR BAG PART NO. 49671-SK 2279971-501
PER MIL-STD-130.
7. ENGRAVE .V32 WIDE LINE AND ARROWHEAD
APPROXIMATELY 45° DOWN, AT SPECIFIED
ANGLE, FILL WITH WHITE AFTER APPLYING
FINISH.


FOLDOUT FRAMES

SEE NOTE 7

1. L, CSK., TAP & INSTALL
2. MS PER ITEM 5
3. HOLES EQ SPACED
4. 1.938 DIA B.C.



SECTION A-A







FOLDOUT FRAME 2

FOR PARTS LIST SEE PL SK2279971

ITEM NO.	DESCRIPTION	QUANTITY	UNIT
1	GEAR HOUSING (FRONT)	1	EA

GEAR HOUSING (FRONT) E 49671 SK2279971	
DATE 2/71 BY [Signature]	CHECKED [Signature] DATE 2/71



NOTES:



1. SECURE GEAR, ITEM 6 IN POSITION USING SET SCREW, ITEM 23. DRILL .039±.005 DIA HOLE USING PART DRILLED HOLE IN ITEM 6 AS A PILOT. PIN ITEM 6 TO MOTOR SHAFT USING ITEM 24. REMOVE SET SCREW, ITEM 23 AND DISCARD.
2. ROTATE MOTOR TO ADJUST GEAR CENTER DISTANCE. ADJUST FOR MIN .002 TO MAX .004 BACKLASH BETWEEN ITEMS 3 AND 4.
3. BOND ITEMS 9 AND 10 USING ITEMS 25, 26 AND 27 PER ITEM 29.
4. ITEM 9 TO BE FLUSH WITH SURFACE A.

SECTION C-C


SECTION B-B

REPRODUCIBILITY OF THE ORIGINAL PAGE IS POOR

FOLDOUT FRAME



SECTION B-B



REAR VIEW SHOWN
WITH ITEM 2 REMOVED

FOLDOUT TABLE

(FOR PARTS LIST SEE PL SK2279979)

ITEM NO.	DESCRIPTION	QUANTITY	UNIT
1	FLY WHEEL ASSEMBLY	1	EA
2	FLY WHEEL	1	EA
3	FLY WHEEL	1	EA
4	FLY WHEEL	1	EA
5	FLY WHEEL	1	EA
6	FLY WHEEL	1	EA
7	FLY WHEEL	1	EA
8	FLY WHEEL	1	EA
9	FLY WHEEL	1	EA
10	FLY WHEEL	1	EA
11	FLY WHEEL	1	EA
12	FLY WHEEL	1	EA
13	FLY WHEEL	1	EA
14	FLY WHEEL	1	EA
22	FLY WHEEL	1	EA

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND DECIMALS THEREOF OF INCHES UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN MILLIMETERS AND DECIMALS THEREOF OF MILLIMETERS		MATERIALS AND SPECIFICATIONS UNLESS OTHERWISE SPECIFIED MATERIALS ARE TO BE OF THE FOLLOWING GRADES:	
DIMENSIONS DECIMALS FRACTIONS DECIMALS FRACTIONS DECIMALS FRACTIONS	DIMENSIONS DECIMALS FRACTIONS DECIMALS FRACTIONS DECIMALS FRACTIONS	DIMENSIONS DECIMALS FRACTIONS DECIMALS FRACTIONS DECIMALS FRACTIONS	DIMENSIONS DECIMALS FRACTIONS DECIMALS FRACTIONS DECIMALS FRACTIONS
FILTER WHEEL MODULE ASSEMBLY		RGA	
PART NO. 49671		SK2279979	
REV. 2/79		(SHIT OF 1)	

REPRODUCIBILITY OF THE
ORIGINAL PAGE IS POOR

				SIZE	CODE IDENT NO.	DRAWING NO.	REVISION	SHEET
				A	49671	SKPL2279979	-	2

ITEM	QUANTITY REQUIRED				TYPE	U M	PARTS LIST	
	-504	-503	-502	-501			CODE IDENT	NOMENCLATURE OR DESCRIPTION
5	1			1			1971381-2	MOTOR
1				1			SK2274971-501	GEAR HOUSING (FRONT)
2				1			SK2273447-1	GEAR HOUSING (REAR)
3				1			SK2273467-501	FILTER WHEEL ASSY
4				1			SK2277726-1	RETAINER, LENS
5				3			SK2277722-1	CLAMP
6				1			SK2277717-501	GEAR
7				1			SK2277722-1	SHIM, LENS-RETAINER
8				1			SK2277701-1	PLATE, SENSOR MOUNTING
9				1			SK2273224-1	FILTER, COMPENSATING
10				1			SK2277742-1	FILTER, BAND PASS
11				1		01692	58388	MAGNETIC SENSOR
12				3		00141	L3-1	GEAR, MOTOR
13				3		00141	4410	SCREW, SHOULDER
14				3		00141	4710	SCREW, THUMB
15				6			NAS1352C04-10	SCREW
16				6			NAS1640-4	WASHER, LOCK
17				1		00141	D5-1	WASHER, WAVE SPRING
18				1			NAS620-4	WASHER, FLAT
19				1			SK2273306-1	PUSHING, THRUST
20				1			NAS1271C04/1	NUT, SELF LOCKING
21				2		01692	633513	NUT, .250-40
22				3		00141	Y11-3	SCREW, SET
23				1		00141	Y11-8	SCREW, SET
24				1		00141	C5-15	PIN, SPIROL
25				AK			99354-171	RTV 560
26				AK			99354-125	T12 CATALYST
27				AK			90485-120	RTV PRIMER
28				X			8030022	SPEC WORKMANSHIP
29				X				SPEC BONDING

* DENOTES VENDOR ITEMS - SEE SOURCE CONTROL OR SPECIFICATION CONTROL DRAWING BEFORE ORDERING.

UM - IN COLUMN HEADING DENOTES UNITS OF MEASURE (USE STANDARD ABBREVIATION)

EXPLANATION OF SYMBOLS IN TYPE COLUMN


Z - DENOTES CONTROLLED ITEM (CLASSIFIED)

T - DENOTES TOOL DRAWING

J - FOR QUANTITY AND EFFECTIVITY REFER TO EFFECTIVITY BLOCK


CLASSIFICATION:


REV 560971



FOLDOUT FRAME

UNLESS OTHERWISE SPECIFIED,
ALL RESISTOR VALUES ARE IN OHMS.
ALL DIODES ARE IN 45.
ALL TRANSISTORS ARE 2N222A.
ALL CAPACITOR VALUES ARE IN pF.
NOTES:






4

1370

REV	DATE	DESCRIPTION	DATE	APPROVED
A	4-24-74	ADDED C SEE NOTE 2 ADDED B SEE NOTE 2 ADDED NOTES 2 & 3 RMH		2.0.13





FOLDOUT FRAME 2

SECTION A-A

QTY REQD PER DASH NO.	CODE IDENT	IDENTIFYING NO.	DESCRIPTION	SPECIFICATION	SEE NOTE NO.
	X	1930135-1	CHEM TREAT	MIL-C-5541B	
	X	8030022	SPEC. WORKMANSHIP		
	AR	1930043-1	BLACK ANODIZE		
	AR	2010636-597	AL ALY (2024-T4) PLATE 1.0TH	QQ-A-250/4C	
	-I				

UNLESS OTHERWISE SPECIFIED THE SURFACE FINISH OF MACHINED PARTS SHALL NOT EXCEED A MAXIMUM READING 125 PER ANSISTD B46.1 - 1962		UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING		CONTRACT NO. N59-13688		DATE 12/15/74		RCA CORPORATION - NEW YORK, NY	
INTERPRET DIMENSIONS AND TOLERANCES PER ANSI Y14.5-66		TOLERANCES ON		CHECKED BY [Signature]		DATE 12/15/74		GEAR HOUSING (REAR)	
THIS DATA TO BE INTERPRETED USING NBS HDBK H29 AND MIL STD 9		BASIC DIMENSIONS		2 PLACE DECIMALS		3 PLACE DECIMALS		SCALE 2/1	
		UP TO 6		= .02		= .010		WEIGHT	
		6 TO 24		= .03		= .015		SHEET 1 OF 1	
		ABOVE 24		= .06		= .020			
		ANGULAR DIMENSIONS		- 1/2					
SK2279973 SHUTTLE T.V.		RCA COMMODITY CODE		DATE 12/15/74		SIZE D		CODE IDENT NO. 49671	
NEXT ASSY USED ON								SK2283447	
FIRST APPLICATION									

DASH NO.	SPECIFICATION TABLE		
	MATERIAL	FINISH	SPECIFICATION



DASH-1

NOTES:

FOR ALL DASH NUMBERS


1. MATERIAL - PHOSPHOR BRONZE SHEET .006 THK, QQ-B-750 (2), 49671-2010016-156.
2. ETCH TO PATTERN INDICATED (AREAS IN BLACK DESIGNATE MATERIAL).
3. FINISH - CHEMICAL BLACK FOR BRASS 1980176-1.
4. TAG OR BAG PART NO. 49671-SK2283465-□□ PER MIL-STD-130.

FOLDOUT FRAM

REPRODUCIBILITY OF THE
FINAL PAGE IS POOR

THIS DATA TO BE INTERPRETED USING INDEX H28 AND MIL STD 9		RECU
RCA COMMODITY CODE		



REDUCE TO $1.000 \pm .005$



DASH-2

FOLDOUT FRAME

REVISIONS			
DATE	LTD	DESCRIPTION	DATE
			APPROVED



FOLDOUT ~~TABLE~~ *13*

SIZE	CODE IDENT NO.	
D	49671	SK2283465
SCALE 10/1	WEIGHT	SHEET 2 OF 6

D

REDUCE TO $1.000 \pm .005$


C

A

B

DASH-3

FOLDOUT FRAME /



REVISIONS			
ZONE	LTN	DESCRIPTION	DATE
			APPROVED

SK2283465 2

SIZE	CODE IDENT NO.	
D	49671	SK2283465
SCALE	10/1	WEIGHT
		SHEET 3 OF 6

8


1

0

5

7

← REDUCE TO 1.000 ± 0.005 →





DASH-4

FOLDOUT FRAME /



REVISIONS			
ZONE	LTR	DESCRIPTION	DATE
			APPROVED



ENCLOSURE FRAME

SIZE	CODE IDENT NO	
D	49671	SK2283465
SCALE	0/1	WEIGHT

SHEET 4 OF 6

D
O
A
B
E
F
G
H
I
J
K
L
M
N
O
P
Q
R
S
T
U
V
W
X
Y
Z

SK2283465

8

7

6

5

4

D


REDUCE TO $1.000 \pm .005$ 

C

→

B


A



DASH-5

FOLDOUT FRAME /

↑



REVISIONS			
ZONE	LTR	DESCRIPTION	DATE
			APPROVED

FOLLOW UP DRAWING

SIZE	CODE IDENT NO.	
D	49671	SK2283465
SCALE	10/1	WEIGHT
		SHEET 5 OF 6



8

7

6

5

4



DASH-6

FOLDOUT FRAME



4

3

2

1


REVISIONS			
ZONE	LTH	DESCRIPTION	DATE
			APPROVED



HOLDOUT FRAME 12

SIZE	CODE IDENT NO	
D	49671	SK2283465
SCALE	10/1	WEIGHT
		SHEET 6 OF 6






REPRODUCIBILITY OF THE
ORIGINAL PAGE IS POOR

NOTES:

1. BOND ITEMS 9 THRU 15 TO ITEM 1, USING ITEMS 16, 17 AND 18 PER ITEM 20. VENT CAVITIES BETWEEN FILTERS BY LEAVING A VOID IN THE POTTING AT THE TOE OF THE SEGMENTS.
2. BOND ITEMS 14 AND 15 TO OUTER FACE OF ITEMS 12 AND 13. BUILDUP FROM WHEEL FACE .005 MAX.
3. ITEM 14 SELECTED TO BALANCE CHANNEL OUTPUTS PRIOR TO BONDING PER NOTES 1 & 2.
4. ADJUST SHIM (ITEM 5) TO PROVIDE 1.5 LB. ± .25 PRELOAD ON BEARINGS (ITEM 2).

5. ADJUST INDIVIDUAL FILTER POSITION DURING BONDING, SO THAT AFTER BONDING, THE MAXIMUM TRANSMITTED IMAGE SHIFT BETWEEN ANY TWO FILTER SEGMENTS SHALL NOT EXCEED 0.01 MM.

WELDOUT AREA



SECTION A-A

FOR PARTS LIST SEE PL SK2283469

QTY REQD PER DASH NO.	CODE IDENT	IDENTIFYING NO.	DESCRIPTION	SPECIFICATION	SEE NOTE NO.

MATERIALS AND SPECIFICATIONS

UNLESS OTHERWISE SPECIFIED THE SURFACE FINISH OF MACHINED PARTS SHALL NOT EXCEED A MAXIMUM READING 125/PER ANSI STD B46.1 — 1962 INTERPRET DIMENSIONS AND TOLERANCES PER ANSI Y14.5 CG THIS DATA TO BE INTERPRETED USING NDS HDBK H20 AND MIL-STD-9		UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND INCLUDE THICKNESS OF PLATING TOLERANCES ON <table border="1"> <thead> <tr> <th>BASIC DIMENSIONS</th> <th>2 PLACE DECIMALS</th> <th>3 PLACE DECIMALS</th> </tr> </thead> <tbody> <tr> <td>UP TO 6</td> <td>± .02</td> <td>± .010</td> </tr> <tr> <td>6 TO 24</td> <td>± .03</td> <td>± .015</td> </tr> <tr> <td>ABOVE 24</td> <td>± .06</td> <td>± .020</td> </tr> </tbody> </table> ANGULAR DIMENSIONS ± 1°		BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS	UP TO 6	± .02	± .010	6 TO 24	± .03	± .015	ABOVE 24	± .06	± .020	CONTRACT NO. NAS9-13688 DATE MAY 14, 1974 DESIGNED BY R. J. Saffar CHECKED BY M. E. Hickey DATE MAY 29, 1974		BIA CORPORATION NEW YORK, NY ASTRO-ELECTRONICS DIVISION, PRINCETON, N.J. PLANT	
BASIC DIMENSIONS	2 PLACE DECIMALS	3 PLACE DECIMALS																	
UP TO 6	± .02	± .010																	
6 TO 24	± .03	± .015																	
ABOVE 24	± .06	± .020																	
SK2279979 SHUTTLE TV NEXT ASSY USED ON FIRST APPLICATION		RCA COMMODORE CODE		DESIGN ACTIVITY APPD. DATE SCALE 4/1 WEIGHT SHEET 1 OF 1															
				FILTER WHEEL ASSEMBLY D 49671 SK2283469															

DATE	APPROVED
9-9-74	D. H. H. H.
10-11-74	D. H. H. H.

[illegible]

MATERIALS AND SPECIFICATIONS

PLAN

SIZE	CODE IDENT NO.	SK2283875
D	49671	

SCALE		SHEET 1 OF 1
-------	--	--------------

FIRST APPLICATION